South Carolina Department of Transportation On Behalf of the Federal Highway Administration - South Carolina Division Office PROCESSING FORM FOR PROGRAMMATIC CATEGORICAL EXCLUSIONS NON MAJOR FEDERAL ACTIONS										
State ID	State ID P040306 Fed Project # Route SC 4 County Aiken									
Part 1 - Project Description										
Include th	Include the Project Name/Description									
failures. T feet wide fills to the	This project proposes to replace the SC 4 bridge over the South Forth Edisto river. The bridge is currently closed due to structural failures. The existing bridge is approximately 600 feet long and 28 feet wide. The new bridge will be approximately 620 feet long and 44 feet wide meeting current design standards. The project will be constructed on alignment and utilize a close and detour route. Minimal fills to the existing roadway embankment will occur in order to comply current bridge design standards.									
Part 2 - PCE Type										
Select the menu. Re 771.117.	e appropriate Cat ference Append	egorical Exclusio lix A of the PCE	on from 23 CFR Pa Agreement for a	art 771.1 a more d	17 that best fits the e letailed description	entire project from of each CE conta	the drop-down ined in 23 CFR			
23 CFR 77	23 CFR 771.117(c) Bridge rehabilitation, reconstruction, or replacement or railroad crossing improvements									
23 CFR 771.117(d)										
Part 3 - Thresholds										
To be processed as a Programmatic Categorical Exclusion (PCE) the following conditions must be met in addition to the General Criteria (as outlined in the PCE Agreement between FHWA-SC and SCDOT). Place a "X" in the appropriate box below. If the answer is "Yes" to any of the below criteria, SCDOT will consult with FHWA-SC to determine the appropriate level of NEPA documentation required and forward to FHWA-SC for approval. *Reference Part 4 of the Processing form or Section IV of the PCE Agreement for more details and definitions regarding each threshold.										
1. In	volves any unusua	I circumstances as	described in * <u>23 C</u>	CFR Part 7	71.117(b)	Yes	No No			
2. Tł of	ne acquisition of m right-of-way	ore than * <u>minor a</u>	mounts of tempora	ary or per	manent strips	☐ Yes	🔀 No			

	Part 3 - Thresholds Continued							
3.	Involves acquisitions that result in residential or non-residential displacements	Yes	🔀 No					
4.	Results in capacity expansion of a roadway by adding through lanes	Yes	🔀 No					
5.	Involves construction that would result in * <u>major traffic disruptions</u>	Yes	⊠ No					
6.	Involves * <u>changes in access control</u> requiring FHWA approval	Yes	🔀 No					
7.	An adverse effect determination under Section 106 of the National Historic Preservation Act.	🗌 Yes	🔀 No					
8.	Use of Section 4(f) property that cannot be documented with a FHWA <i>de minimis</i> determination or a programmatic Section 4(f) other than the programmatic evaluation for the use of historic bridges	Yes	🔀 No					
9.	Any use of a Section 6(f) property	Yes	🖂 No					
10.	Requires an Individual USACE 404 Permit	Yes	🔀 No					
11.	Requires an Individual U.S. Coast Guard Permit.	Yes	🔀 No					
12.	Work encroaching in a regulatory floodway, adversely affecting the base floodplain (100 yr.) pursuant to E.O. 11988 and 23 CFR Part 650 Subpart A	Yes	🔀 No					
13.	Construction in, across, or adjacent to a river designated as a National Wild and Scenic River	Yes	🔀 No					
14.	Involves an increase of 15 dBA or greater on any noise receptor or abatement measures are found to be feasible and reasonable due to noise impacts	Yes	🔀 No					
15.	May affect and is likely to adversely affect a Federally listed species or designated critical habitat or projects with impacts subject to the BGEPA	Yes	🔀 No					
16.	Involves acquisition of land for hardship, protective purposes, or early acquisition	Yes	🔀 No					
17.	Does not meet the latest Conformity Determination for air quality non-attainment areas (if applicable).	Yes	🔀 No					
18.	Any known or potential <u>major</u> hazardous waste sites within the right-of-way.	Yes	🖂 No					
19.	Is not included in or is inconsistent with the STIP and/or TIP	Yes	🖂 No					

Part 3 Continued - Ad	ditional criteria	to be complete	d for disposal o	of excess right	t-of-way F	PCE		
1. Is the parcel part of a SCDOT mitigation?	environmental mitic	gation effort or could i	be used for environ	mental	🗌 Yes	🗌 No		
2. Is there a formal plan to use	2. Is there a formal plan to use this parcel for a future transportation project (is it part of an approved LRTP)?							
	Part	: 4 - Threshold [Definitions					
Unusual Circumstances (23 C	FR Part 771.117) - ।	Jnusual circumstance	are defined as:					
a. Significant environmental im b. Substantial controversy on e c. Significant impact on proper d. Inconsistencies with any Fec of the action.	ipacts; invironmental groun ties protected by Sec leral, State, or local la	ds; ction 4(f) of the DOT A w, requirement, or ad	CT or Section 106 of t ministrative determir	the National Histor nation relating to t	ic Preservatio he environme	n Act; or ental aspects		
Minor Amount of Right-of-W	ay (ROW):							
A minor amount of ROW is defi projects (eg: intersections, brid residential and business struct of minor improvements, such a	A minor amount of ROW is defined as less than 3 acres per linear mile for linear projects or less than 10 acres of impacts for non-linear projects (eg: intersections, bridges), and no removal of major property improvements. Examples of major improvements include residential and business structures, or the removal of other features which would change the functional utility of the property. Removal of minor improvements, such as fencing, landscaping, sprinkler systems, and mailboxes would be allowed.							
Major Traffic Disruptions:								
A major traffic disruption is def substantial change in environn closure. Changes in Access Control:	ined as an action tha nental impacts, or c)	at would result in: a) ac public controversy ass	lverse effects to throu ociated with the use	ugh-traffic busines of the temporary r	ses or school: oad, detour, o	s, b) or ramp		
Requires approval from FHWA Justification Reports).	for changes in acces	s control on the Inters	ate system (eg: Inter	change Modificatio	on Reports or	Interchange		
Additional Comments	s if Needed:							
The river at this location has b Programmatic Biological Evalu regarding sturgeon critical ha	een deemed critical Jation (NLAA) as agre bitat. Documentatio	habitat for sturgeon b eed upon by FHWA an n is attached.	y NMFS. SCDOT has o d NMFS dated Septer	coordinated with N mber 2018 to satisf	MFS and is ut fy coordinatic	ilizing the on efforts		
Relevant field studies and en forth in the Programmatic C additions/deletions to the p engineering changes must h form is included in the proje	nvironmental revies ategorical Exclusio roject may void en be bought to the at ect file and one (1) o	ws have been comp n Agreement signed vironmentally proce ttention of SCDOT E copy has been provi	leted to determine I by FHWA-SC and S ssing the project as nvironmental Servio ded to FHWA.	that the project SCDOT. It is unde s presently classif ces Office immed	meets the cr erstood that fied; conseq iately. A cop	iteria set any uently, any oy of this		
Prepared By: Will M	cGoldrick	Digitally signed by Wi Date: 2021.01.26 11:	I McGoldrick 66:54 -05'00'] Date Jan	26, 2021			

Jan 13, 2021

P2S Date:

Does the project contain

commitments?: (if Yes attach to form) 🛛 Yes

🗌 Yes

🖂 No

Primavera:

🗌 No

Date: 01/26/2021	NEPA ENVIRONMEN	TAL COMMITMENTS FOR	M	ENVIRONMENDEL SERVICES				
Project ID : P040306 County :	Aiken Distr	ict : District 7 Doc 7	ype: PCE	Total # of 9				
Project Name: SC 4 Bridge Replacement over the South Fork Edisto River								
The Environmental Commitment Contractor Responsible measures listed below are to be included in the contract and must be implemented . It is the responsibility of the Program Manager to make sure the Environmental Commitment SCDOT Responsible measures are adhered to. If there are questions regarding the commitments listed please contact:								
CONTACT NAME: Brad Reynolds PHONE #: 8037371440								
ENV	IRONMENTAL COM	MITMENTS FOR THE I	PROJECT					
USTs/Hazardous Materials	NEPA Doc Ref:		Responsibility:	CONTRACTOR				
If avoidance of hazardous materials i during construction, the South Caro Hazardous materials will be tested Protection Agency and the SCDHEC re	s not a viable alterna lina Department of and removed and/or quirements, if necess	ative and soils that app Health and Environme r treated in accordance ary.	ear to be contam intal Control (SCE ie with the Unite	inated are encountered OHEC) will be informed. d States Environmental				
				Special Provision				
Water Quality	NEPA Doc Ref:		Responsibility:	CONTRACTOR				
The contractor will be required to minimize possible water quality impacts through implementation of BMPs, reflecting policies contained in 23 CFR 650B and the Department's Supplemental Specification on Erosion Control Measures (latest edition) and Supplemental Technical Specifications on Seeding (latest edition). Other measures including seeding, silt fences, sediment basins, etc. as appropriate will be implemented during construction to minimize impacts to water quality.								
				Special Provision				
Migratory Bird Treaty Act	NEPA Doc Ref:		Responsibility:	CONTRACTOR				
The federal Migratory Bird Treaty Act, 16 USC § 703-711, states that it is unlawful to pursue, hunt, take, capture or kill; attempt to take, capture or kill; possess, offer to or sell, barter, purchase, deliver or cause to be shipped, exported, imported, transported, carried or received any migratory bird, part, nest, egg or product, manufactured or not. The South Carolina Department of Transportation (SCDOT) will comply with the Migratory Bird Treaty Act of 1918 in regard to the avoidance of taking of individual migratory birds and the destruction of their active nests.								
The contractor shall notify the Resident Construction Engineer (RCE) at least four (4) weeks prior to construction/demolition/maintenance of bridges and box culverts. The RCE will coordinate with SCDOT Environmental Services Office (ESO), Compliance Division, to determine if there are any active birds using the structure. After this coordination, it will be determined when construction/demolition/maintenance can begin. If a nest is observed that was not discovered after construction/demolition/ maintenance has begun, the contractor will cease work and immediately notify the RCE, who will notify the ESO Compliance Division. The ESO Compliance Division will determine the next course of action.								
The use of any deterrents by the contractor design The cost for any contractor provided deterrents will	ed to prevent birds from nes be provided at no additional	ting, shall be approved by the cost to SCDOT.	RCE with coordination fr	om the ESO Compliance Division.				

Project ID :	P040306
--------------	---------

SCDOT NEPA ENVIRONMENTAL COMMITMENTS FORM



ENVIRONMENTAL COMMITMENTS FOR THE PROJECT

Stormwater	NEPA Doc Ref:		Responsibility:	CONTRACTOR			
Stormwater control measures, both during construction and post-construction, are required for SCDOT projects with land disturbance and/or constructed in the vicinity of 303(d), TMDL, ORW, tidal, and other sensitive waters in accordance with the SCDOT's MS4 Permit. The selected contractor would be required to minimize potential stormwater impacts through implementation of construction best management practices, reflecting policies contained in 23 CFR 650 B and SCDOT's Supplemental Specifications on Seed and Erosion Control Measures (latest edition).							
Cultural Resources NEPA Doc Ref: Responsibility: CONTRACTOR							
The contractor and subcontractors must notify their workers to watch for the presence of any prehistoric or historic remains, including but not limited to arrowheads, pottery, ceramics,flakes, bones, graves, gravestones, or brick							

concentrations during the construction phase of the project, if any such remains are encountered, the Resident Construction Engineer (RCE) will be immediately notified and all work in the vicinity of the discovered materials and site work shall cease until the SCDOT Archaeologist directs otherwise.

|--|

Lead-Based Paint	NEPA Doc Ref:		Responsibility:	CONTRACTOR
The existing structures shall be removed a Standard Specifications. The Contractor's structural components containing lead-bas paints shall comply with all applicable Fed in soil, and worker health and safety.	and disposed of by s attention is called sed paints. Remov leral, State, and Lo	the Contractor in accord to the fact that this projetal and disposal of structure ocal requirements for lead	dance with Subse ect may require re ural components d as waste, lead	ection 202.4.2 of the emoval and disposal of containing lead-based in air, lead in water, lead
				Special Provision

Project ID :	P040306
--------------	---------

SCDOT
NEPA ENVIRONMENTAL COMMITMENTS
FORM



ENVIRONMENTAL COMMITMENTS FOR THE PROJECT

Non-Standard Commitment	NEPA Doc Ref:		Responsibility:	SCDOT
Permitting				
SCDOT will obtain the necessary permits fo SC Department of Health and Environment by the USACE approved SCDOT General Per	or completion of the al Control (SCDHEC mit.	e project including the US A) Navigable Waters permits	rmy Corps of Er lt is anticipate	ngineers 404 (USACE) and d impacts will be covered
				Special Provision

Non-Standard Commitment	NEPA Doc Ref:		Responsibility:	CONTRACTOR
Floodplains				
The project will be designed in an effective floodplain impacts will be coordinated agencies as necessary.	ort to meet "No-F d with the local c	Rise" requirements. Fir ounty NFIP representa	nal design effor tive and approp	ts to minimize priate regulatory
				Special Provision

Non	-Standard Commitment	NEPA Doc Ref:		Responsibility:	CONTRACTOR
FH	WA-NMFS Biological Evaluation Program	imatic Agreement C	onditions		
Th FF lik of	The South Fork Edisto River is designated by NOAA-National Marine Fisheries (NMFS) as critical habitat for Atlantic Sturgeon. The FHWA-NMFS Programmatic Agreement (PA) outlines Project Design Criteria (PDC) that must be met to achieve a "may affect, not likely to adversely affect Section 7 determination. SCDOT and/or the CONTRACTOR shall comply with all PDCs during construction of the project and implement necessary best management practices (BMPs) as prescribed in the PA.				
					[

Species Coordination

Bridge Replacement on SC Route 4 over the South Fork of Edisto River in Aiken County, South Carolina

Prepared by Biologist: ______ Cdward W. Frierson

Pursuant to Section 7 of the Endangered Species Act a field survey was conducted on the proposed project corridor. The Bald eagle is protected by the Bald and Golden Eagle Protection Act (BGEPA). The following list of endangered (E) and threatened (T) species was obtained from the U. S. Fish and Wildlife Service (USFWS):

ANIMALS

American wood stork – *Mycteria americana* – (T) Bald eagle – *Haliaeetus leucocephalus* – (BGEPA) Red-cockaded woodpecker – *Picoides borealis* – (E) Atlantic sturgeon – *Acipenser oxyrinchus* – (E) Shortnose sturgeon – *Acipenser brevirostrum* – (E)

PLANTS

Harperella – *Ptilimnium nodosum* – (E) Relict trillium – *Trilllium reliquum* – (E) Smooth coneflower – *Echinacea laevigata* – (E)

METHODS

The project area was examined utilizing reconnaissance methods on January 6, 2021. In addition, GIS was utilized for any past sightings that may have occurred in the area. Habitats surveyed were determined by each species ecological requirements.

RESULTS

The improvements will require both upland forested areas and palustrine forested wetlands. The south fork of the Edisto River which is a riverine unconsolidated bottom wetland is traversed by the bridge. The upland forested areas are characterized by loblolly pine (*Pinus taeda*), common sweetleaf (*Symplocos tinctoria*), and yellow ragwort (*Packera anonyma*). The palustrine forested wetlands are characterized by bald cypress (*Taxodium distichum*), willow oak (*Quercus phellos*), and common reed (*Phragmites australis*).

Even though there is a relatively large body of water present, no habitat for either the Bald eagle or wood stork was located. Bald eagles prefer more open habitat and wood stork prefers shallower and more open waters. No habitat for the red cockaded woodpecker is in the project area. Potential habitat for relict trillium was located but no specimens were observed. No habitat for the coneflower or Harperella was located in the project corridor. The south fork of the Edisto River has been listed as critical habitat for the Atlantic sturgeon and is also habitat for the short nose sturgeon though not critical. Therefore, the project may affect but not adversely affect the Atlantic and shortnose sturgeon. Coordination with the National Marine Fisheries Service is presently being conducted to get concurrence with this finding. Therefore, except for the two sturgeon species, the proposed action will have no effect on any protected species currently listed by the USFWS for Aiken County.

From:	Robert Hoffman - NOAA Federal
To:	Belcher, Jeffery - FHWA
Cc:	McGoldrick, Will
Subject:	Re: FHWA-SC: SC 4 Bridge over the South Edisto; NOAA/FHWA ESA Regional PA
Date:	Thursday, January 14, 2021 12:48:21 PM

*** This is an EXTERNAL email. Please do not click on a link or open any attachments unless you are confident it is from a trusted source. ***

Based on the information you sent, I believe this qualifies for use of the Programmatic Consultation.

On Thu, Jan 14, 2021 at 8:46 AM Belcher, Jeffrey (FHWA) <<u>Jeffrey.Belcher@dot.gov</u>> wrote:

Robert,

FHWA and SCDOT submits the subject project to be processed under the FHWA and NOAA ESA Regional Agreement. The project consists of replacing the current SC 4 Bridge over the South Edisto River in Aiken County South Carolina. The proposed project is located within critical habitat for the Atlantic sturgeon. The bridge is currently closed to traffic due to structural issues. SCDOT proposes to replace the bridge through FHWA's Emergency Relief Program. The replacement bridge, as proposed, will span the South Edisto and no piles/columns will be placed in the river. Attached is the required spreadsheet along with a list of all Project Design Criteria (PDC) that would be applicable to the project under the Regional ESA Agreement that will be complied with during construction. Also attached is a plan sheet and photos of the existing bridge. The proposed project will be constructed through a design-build contract, so no set of plans is available for the new bridge. The contractor however, would be required to design the bridge to span the river.

For consultation on this project, I will be the contact for FHWA (my contact info is below) and Mr. Will McGoldrick (<u>McGoldriWR@scdot.org</u>) will be the primary contact for SCDOT. Since this is the first use of the PA for South Carolina, we would be glad to discuss any details regarding the project or any of the information we have provided.

Much thanks,

J. Shane Belcher

Lead Environmental Specialist

Federal Highway Administration

1835 Assembly Street, Suite 1270

Columbia, SC 29201

Phone: 803-253-3187

The content of this email is confidential and intended for the recipient specified in message only.

--Bob Hoffman Sea Turtle and Fisheries Branch Chief

All Activities/Projects			
SCDOT SC 4 Bridge Replacement (P040306) over South Fork Edisto River FHWA-NMFS Programmatic			
Agreement Application Form			
Title	Format	Description	
Date Sent to NMFS	1/14/2021	This is the date the email with the project review	
		information was sent to NMFS	
FHWA PM/POC Last	Belcher	Provide your last name only	
Name			
Permit Used	USACE General Permit. Coordination	The permit instrument used to authorize the activity	
	occurring through NEPA phase.		
Any other component of	No	Was any activity authorized under a different	
project issued under		programmatic or separate Section 7 consultation?	
different permit			
instrument?			
Identify any other permit	NA	If the answer to previous question was "Yes," then	
instrument used.		describe the permit type used to authorize the other	
		project component.	
Permit Tracking Number	Permit not yet issued.	This is the permit number assigned by USACE to the	
		project.	
Project Address	3522 Wagener Rd, Aiken, SC 29805	Address of the project site	
County	Aiken	County the project site is located	
Latitude	33.576710	This shall be formatted in decimal degrees to 5	
		places.	
Longitude	-81.603363	This shall be formatted in decimal degrees to 5	
		places. Please provide a negative symbol before the	
		longitude to denote the western Hemisphere.	
Waterbody	South Fork Edisto	Provide easily identifiable name/names of waterbody	
		where project will take place.	
Seagrass(es) in project	No	Type "Yes" if seagrasses are located within the	
footprint?		project footprint.	
Impacts to seagrass(es)?	NA	Calculate the square feet of impacts to seagrasses.	
Located in Atlantic	82 FR 39160	Provide the critical habitat unit that the project occurs	
Sturgeon Critical Habitat		within the boundaries of critical habitat even if it	
Unit?		does not impact the essential features or select "N/A"	
		if not located in geographic area of any critical	
		habitat under NMFS PRD purview.	
Atlantic Sturgeon CH	0 sq ft [channel will be spanned by	Calculate the square feet of impacts to essential	
Impacts to Physical and	new bridge. no new piles in river.]	features. Review the document for the definition of	
Biologcal Features.		essential features.	

Section/Reference	Criteria	
4.1.1 General Project Design Criteria (PDC) Applicable to All Projects		
	Wetland avoidance/minimization/compensation	
	Clearly delineating vegetative clearing limits; maintaining riparian	
	buffers/minimizing impacts to riparian buffers.	
	Compliance with State water quality standards through Storm Water	
	Pollution Prevention Plans (SWPPP), which include erosion and sediment	
	control, spill control, runoff detention, and treatment (further described	
	in AP4.)	
	AP1. All projects will adhere to the sea turtle measures in the most current version of NMFS's Sea Turtle and Smalltooth Sawfish Construction Conditions, when a project is located in areas where sea turtles occur. These conditions will also apply to projects located in areas where Atlantic and shortnose sturgeon occur (the Conditions include protections for listed species in general). This includes the requirement that construction stops temporarily if an ESA-listed species is sighted within 50 feet of mechanical construction equipment	
	AP2. Vessel Traffic and Construction Equipment: All vessel operators will watch for and avoid collision with species protected under the ESA. Vessel operators will avoid potential interactions with protected species and operate in accordance with the following protective measures:	
Construction Equipment:	AP2.1. All vessels associated with the construction project will operate at "Idle Speed/No Wake" at all times while operating in water depths where the draft of the vessel provides less than a 4-foot (ft) clearance from the bottom, and after a protected species has been observed in and has departed the area.	
	AP2.2. All vessels will follow marked channels and/or routes using the maximum water depth whenever possible.	
	AP2.3. Operation of any mechanical construction equipment, including vessels, will cease immediately if a listed species is observed within a 50-ft radius of construction equipment and cannot resume until the species has departed the area of its own volition.	
Turbidity		
	AP3. Turbidity Control Measures during Construction: Turbidity must be monitored and controlled. Prior to initiating any of the work covered under this programmatic consultation, the Permittee will install turbidity barriers (including fencing and curtains) as described below. In some instances, the use of turbidity curtains may be waived if the project is deemed too minimal to generate turbidity or if the current is too strong for the curtains to stay in place or if the water is too shallow for a curtain. Turbidity barrier specifications:	

	AP3.1. Use turbidity barriers throughout construction to control erosion
	and siltation and ensure that turbidity levels within the project area do
	not exceed background conditions (i.e., the normal water quality levels
	from natural turbidity)
	Ap2.2. Desition to whidity berging in a way that does not block encoded.
	AP3.2. Position turbidity barriers in a way that does not block species
	entry to or exit from designated critical habitat.
	AP3.3. Install floating turbidity curtains with weighted skirts around all
	work areas that are in, or adjacent to, surface waters. All turbidity
	curtains should extend to 1 ft. or less from the bottom (acceptable to lay
	on the bottom, especially at low tides).
	AP3.4 Monitor and maintain turbidity barriers in place until the
	authorized work has been completed and the water quality in the
	autionized work has been completed and the water quality in the
	project area has returned to background conditions.
	APA Potroloum products, chamicals, live (unsured) concrete, as water
Contaminator	contaminated by these will not be allowed to enter flowing water
Contaminates	contaminated by these will not be allowed to enter howing waters.
	AD4.1 To the maximum autent practicable, refugling of machinery will be
	AP4.1 To the maximum extent practicable, refueling of machinery will be
	done at least 250 feet from any water body and be outside of active
	stream channels, outside of any tidal areas, and away from ditches or
	channels that enter flowing waters; designated refueling sites in upland
	areas at least 250 feet away from receiving waters are preferred.
	Refueling of boats and heavy machinery such as cranes positioned atop
	temporary work platforms over the water will take all relevant
	precautions to avoid spills into waterbodies.
	AP4.2 To the maximum extent practicable, concrete washout
	pits/pans/pools will be located at least 500 feet from any water body
	and be outside of active stream channels, outside of any tidal areas, and
	away from ditches or channels that enter flowing waters. Designated
	sites in upland areas at least 500 feet away from receiving waters are
	preferred.
	AP4.3 A Spill Plan will be created, and the plan and all materials
	necessary to implement the plan shall be accessible on site.
	AP5. Construction personnel will ensure all materials placed in the
	water, including sheet piles, concrete piles, and erosion control
	materials, will be free of sediments and/or contaminants
	AP6. Reporting of interactions with protected species:
	AP6.1. Any collisions(s) and/or injuries to any sea turtle or sturgeon
	occurring during the construction of a project, will be reported
	immediately to NMES's Protected Resources Division (PRD) at (1-727-
	824-5312) or by email to takerenort nmfsser@noaa.gov. Sea turtle
	stranding/rescue organizations' contact information is available by
	region at http://www.pmfc.paca.gov/ar/health/activer/c/htm
1	region at http://www.nmis.noaa.gov/pr/nealtn/networks/ntm.

AP6.2. Dead sturgeon must be reported to 1-844-788-7491 or email nmfs.ser.sturgeonnetwork@noaa.gov

AP7 Entanglement: All turbidity curtains and other in-water equipment will be properly secured with materials that reduce the risk of entanglement of marine species (described below). Turbidity curtains likewise will be made of materials that reduce the risk of entanglement of marine species.

AP7.1. In-water lines (rope, chain, and cable, including the lines to secure turbidity curtains) will be stiff, taut, and non-looping. Examples of such lines are heavy metal chains or heavy cables that do not readily loop and tangle. Flexible in-water lines, such as nylon rope or any lines that could loop or tangle, will be enclosed in a plastic or rubber sleeve/tube to add rigidity and prevent the line from looping and tangling. In all instances, no excess line will be allowed in the water.

AP7.2. Turbidity curtains and other in-water equipment will be placed in a manner that does not entrap species within the construction area or block access for them to navigate around the construction area.

AP8. All projects will follow the PDCs defined in Section 5.2 ("Noise") and Appendix A. .

AP8.1. Projects will not result in noise in excess of the established thresholds for physical injury or behavioral modification (single strike and cumulative exposure) for ESA-listed sea turtles and sturgeon. FHWA/State DOTs will ensure all pile installation activities not exceed these thresholds, but may accomplish this using relevant best management practices and other methods to avoid and minimize hydroacoustic impacts. A series of pile types, sizes, and hammer types have been analyzed in **Section 5.2 and Appendix A**, for use as reference/models. Projects that adhere to these previously analyzed scenarios will not need further review. However, projects that do not conform to these previously analyzed scenarios must conduct projectspecific hydroacoustic analyses and submit these analyses to NMFS as part of the programmatic submission document(s). This hydroacoustic information should be clearly marked in a separate section of submittal materials for ease of review.

AP8.2 From January to May and/or August to November, **installation of piles and sheet piles** in rivers where sturgeon are known to use for migration and spawning are limited to drilled-shafts or those activities labeled "A" in section 5.2 ("Noise"). Appropriate/specific timeframes for individual sturgeon migration and spawning rivers are found in Appendix H of the FHWA/NMFS-SERO BMP Manual.

AP10. All in-water work activities will be performed during daylight hours.

1	
412	AP12. All over-water structures will incorporate measures to maximize ambient light transmission and minimize shading. Such measures include, but are not limited to, maximizing the height of the structure and minimizing the width of the structure, minimizing the number of instream pilings/piers, and using grated decking material. The optimal height-width (HW) ratio of newly constructed (new or replacement) bridges, piers, multi-use paths, or docks is 0.7 or greater. This ratio is also recommended for temporary work structures such as trestle systems/work bridges. (See P2.3.4) AP14. All construction personnel are responsible for observing water- related activities to detect the presence of these species and avoid them.
4.1.2	
Activity #1 – Installation, Maintenance, and Removal of Temporary Erosion, Turbidity, and Sediment Control Devices	A1.1 Temporary erosion, turbidity, and sediment control devices are required to be installed prior to any clearing and grubbing activities, to the maximum extent practicable. In areas where clearing and grubbing is necessary to provide access and area for the installation of temporary erosion, turbidity, and sediment control devices, those devices should be installed immediately following the minimal amount of clearing and grubbing that is necessary.
	A1.2 Temporary erosion, turbidity, and sediment control devices are required on all project-related areas, including off-site use areas, staging areas, and in/around temporary access roads and other areas. A1.3 All devices will be regularly inspected for effectiveness and promptly repaired or replaced if they have been damaged or are ineffective.
	A1.4 All temporary devices designed to control erosion, turbidity, and sedimentation throughout the construction process will be removed immediately following project completion. A1.5 Installation of silt/turbidity curtains will be shore-parallel (anchored
	on the shore at both ends) and may not exceed 550 feet in length; curtains must be securely anchored and will not impede or obstruct movement of listed species.
	A1.6 Silt/turbidity curtains will not extend more than 10-feet waterward from the shoreline. In waterways 40-feet wide or less, silt/turbidity curtains will not encroach more than 25% from the Mean High Water Line (MHWL) in intertidal areas or Ordinary High Water Mark (OHWM) in rivers/streams.
Critical Habitat-specific PDCs	A1.8 Siltation control fence or other stationary measures will be placed parallel to the shoreline and may not be placed waterward of the MHWL or OHWM; measures will not impede or obstruct movement of listed species.
Citical nabilal-specific PDCs.	

	A1.9 Installation of erosion, turbidity, and sediment control devices will not occur in Atlantic Sturgeon critical habitat, where the following PBF is present:
	• Suitable hard bottom substrate (e.g., rock, cobble, gravel, limestone, boulder, etc.) in low salinity waters (i.e., 0.0-0.5 parts per thousand range [ppt]) for settlement of fertilized eggs and refuge, growth, and development of early life stages.
	A1.10 Silt/turbidity curtains will only extend waterward into depths no greater than 1.1 meters (3.6 ft) in main river channels; curtains will not impede/obstruct movement of sturgeon.
Activity #2 - Staging Areas	A2.1 Steering areas will be leasted in unland areas and have an energy into
Activity-specific PDCs for staging areas:	temporary erosion, turbidity, and sediment controls, including, but not limited to stabilized construction exists/entrances and sediment control fence.
	A2.2 Staging areas will not be located in active channels (e.g., streams, tidal creek creeks, or rivers) or open water areas and will not be located in tidal areas (e.g., all staging areas will be located above MHWL); staging areas shall be setback a minimum of 15 feet from the OHWM and MHWL.
	A2.3 Staging area activities will not impede or obstruct movement of listed species.
Critical Habitat-specific PDCs:	
	habitat, where the PBFs are present.
	A2.5 Staging areas will be setback a minimum of 75 feet from the active channel (bankfull width) and MHWL in intertidal areas.
Activity #3 - Site Preparation	
Activity-specific PDCs for site preparation activities:	A3.1 To the maximum extent practicable, site preparation (e.g., earthwork, obstruction removal, etc.) will begin following installation of temporary erosion, turbidity, and sedimentation control measures, including perimeter sediment control fence.
	A3.2 Riparian and shoreline clearing, grading, and preparing that occurs in areas where ESA-listed species are present will be completed by hand or with construction machinery (e.g., mini- excavator or bobcat/skid- steer); whichever method best avoids and minimizes erosion, sedimentation, and turbidity. All appropriate precautions will be taken to avoid and minimize erosion, sedimentation, and turbidity.
	A3.3 Construction machinery will not be located in an active channel or below the OHWM or MHWL for site preparation purposes; machinery may reach (e.g., mini-excavator arm with bucket) approximately 5 ft waterward and 5 ft below the OHWM or MHWL for site preparation purposes. Machinery may be placed atop work structures, such as work trestles, mats, or barges.

	A3.4 In areas where ESA-listed species are present, riparian and
	shoreline vegetation will not be cleared, trimmed, or otherwise altered if
	the area is not essential for project construction or facilitation of
	construction.
	A3.5 Site preparation will not impede or obstruct movement of listed
	species.
Critical Habitat-specific PDCs:	
	A3.6 Clearing will take place by hand or with construction machinery –
	whichever method best avoid and minimizes erosion, sedimentation,
	and turbidity - in Atlantic sturgeon critical habitat areas, where the PBFs
	are present. waterward and 2 ft below the OHWM or MHWL for site
	preparation purposes. Machinery may be placed atop work structures,
	such as work trestles, mats, or barges.
	A3.7 Construction machinery will not be located in an active channel or
	below the OHWM or MHWL in Atlantic sturgeon critical habitat, where
	the PBFs are present, for site preparation purposes; machinery may
	reach (e.g., mini-excavator arm with bucket) approximately 2 ft
Activity #4 - Geotechnical Drilling	
and Hazardous Waste Sampling	
Activity-specific PDCs for	A4 1 Bore holes for geotechnical drilling and bazardous waste sampling
activity-specific PDCs for	are limited to 12 E4 inches in diameter (144 inches2: 1 ft2) and only the
wasta compling activities:	are inflicted to 15.54 inclies in diameter (144 inclies2, 11t2) and only the
waste sampling activities.	initial anount of vegetation cleaning required for access will occur.
	A4.2 Drilling in aquatic, intertidal, or wetland areas will occur from
	existing structures (e.g., bridges, temporary work trestles), barges,
	vessels, or low ground bearing pressure tracked rigs.
	A4.4 All areas will be restored to pre-drilling/pre-sampling conditions
	A4.5 Drilling and sampling will be timed to avoid the presence of
	sturgeon and sea turtles, to the extent practicable; drilling and sampling
	will not impede or obstruct movement of listed species.
Critical Habitat-specific PDCs:	
	A4.6 Geotochnical drilling and bazardous waste campling will not accur
	in Atlantic sturgeon critical babitat, where the following DPE is present:
	• Suitable bard bottom substrate (e.g. rock, sabble, gravel, limestane
	- Suitable natu bottom substrate (e.g., rock, cobble, gravel, ilmestone,
	boulder, etc.) in low samily waters (i.e., 0.0-0.5 parts per thousand
	A CONTRACTOR OF A CONTRACTOR AND A CONTR
	range (ppt)) for settlement of refuilzed eggs and refuge, growth, and
	development of early life stages.
	A4.7 Tracked rigs will not be used in critical habitat, where the PBFs are
	A4.7 Tracked rigs will not be used in critical habitat, where the PBFs are present, unless they are operating atop mats, barges, or other

Activity #6 - Temporary Platforms, Access Fills (including rock/rip rap	
jetties), and Cofferdams	[Activities covered in #6 are for in water work structures]
Activity-specific PDCs for temporary platforms, access fills, and cofferdam activities:	A6.1 All [water dependent] activities will be limited to a total of 120 days or less ("temporary" is defined as 120 days or less), except temporary work platforms/work trestles. Temporary work platforms/work trestles are limited to 24 months or less. A6.2 Temporary platforms/work trestles will be installed/constructed following the PDCs outlined in Section 5.2 ("blaics") below and Appendix
	Tollowing the PDCs outlined in Section 5.2 (Noise) below and Appendix
	Α.
	A6.3 The combined temporary impacts from temporary
	platforms/access fills/cofferdams are limited to a total of 0.5 acres or
	less in waters of the U.S. (e.g., below OHWM or MHWL) for a single,
	complete project. Of the total 0.5 acres of temporary impacts, individual
	activity breakdowns are as follows:
	A6.3.1 Temporary platforms are limited to those with substrate impacts
	A6.3.2 Temporary access fills are limited to 0.5 ac of clean fill (e.g. ripran
	free of debris) in waters of the U.S. (e.g., below OHWM or MHWI) at any
	given time.
	A6.3.3 Individual temporary cofferdams are limited to:
	A. 500 ft2 (0.011 ac) or less in size and a maximum of 2 cofferdams
	(regardless of size) may be installed/in place at any given time; a
	maximum of 8 cofferdams (regardless of size) may be installed for a
	single, complete project.
	or
	B. 1000 ft2 (0.023 ac) or less in size and a maximum of 1 cofferdam
	(regardless of size) may be installed/in place at any given time; a
	maximum of 4 cofferdams (regardless of size) may be installed for a
	single, complete project.
	A6.4 Placement of geotextile barriers is required prior to placement of the platform/access fills to ensure that the fill will be removed
	completely at the end of construction.
	A6.5 Temporary fill materials will be placed in a manner that will not be eroded by high water flows. Temporary fills will be removed in their
	enurely and the affected areas returned to pre- construction conditions/elevations
	A6.6 The navigability of the waterway will remain uninterrupted and freely open for species movement in/out of the area.
	$\Lambda 6.6.1$ Cofferdams and fills will be limited to no more than 50% of the
	width of a waterbody. In tidal areas (e.g., tidal creeks), the width of the
	water body should be considered/measured at mean low water (MLW).

	A6.7 Projects will not appreciably impact surface water flow into or out
	of any waters of the U.S.
	A6.8 Appropriate measures will be taken to maintain normal
	downstream flows and minimize flooding to the maximum extent
	practicable, when temporary structures, work and discharges, including
	cofferdams, are necessary for construction activities, access fills, or
	dewatering of the construction sites.
	A6.9 Temporary steel sheet pile cofferdams will be installed/removed by
	vibratory hammers only.
	A6.10 For temporary inflatable cofferdams, the footprints of the walls
	will be included into the overall impacts area.
	A6.12 Activities are not authorized at the mouths of rivers where
	sturgeon are known to migrate for snawning nurnoses
Critical Habitat-specific PDCs:	stargeon are known to migrate for spawning purposes.
interination inductor specific r bes.	A6 13 Temporary platforms/work trestles in Atlantic sturgeon critical
	habitat where the following DRE is present, are limited to 24 menths or
	liability, where the following PBP is present, are infliced to 24 months of
	1250 ft2 (0.005 earres) er less de net impacts (e.g., tottprint of plintgs) of
	230 ft2 (0.005 acres) of less, do not impede of obstruct sturgeon
	movement, and will be installed outside of the spawning/migration
	season.
	• Suitable hard bottom substrate (e.g., rock, cobble, gravel, limestone,
	boulder, etc.) in low salinity waters (i.e., 0.0-0.5 parts per thousand
	range [ppt]) for settlement of fertilized eggs and refuge, growth, and
	development of early life stages.
	A6.14 Temporary access fills in Atlantic sturgeon critical nabitat, where
	the following PBF is present, are limited to 0.25 acre of total temporary
	impacts or less, and will be installed and removed outside of the
	spawning/migration (moratoria) season(s):
	• Suitable hard bottom substrate (e.g., rock, cobble, gravel, limestone,
	boulder, etc.) in low salinity waters (i.e., 0.0-0.5 parts per thousand
	range [ppt]) for settlement of fertilized eggs and refuge, growth, and
	development of early life stages.
	A6.15 Temporary cofferdams in Atlantic sturgeon critical habitat, where
	the following PBF is present, are limited to 2000 ft2 (0.04 acres) of total
	temporary impacts or less (must adhere to the same individual size
	restrictions as A6.3.3), and will be installed and removed outside of the
	spawning/migration (moratoria) season(s):
	• Suitable hard bottom substrate (e.g., rock, cobble, gravel, limestone,
	boulder, etc.) in low salinity waters (i.e., 0.0-0.5 parts per thousand
	range [ppt]) for settlement of fertilized eggs and refuge, growth, and
	development of early life stages.
Activity #7 - Pile Installation and	
Removal	

1	
	A7.7 Vibratory hammers will be used to remove piles. Piles that cannot
Activity-specific PDCs for pile	be removed with vibratory hammers will be cut off at or below the mud
installation and removal activities:	line.
	A7.8 All holes left by removed piles will be filled with clean, native
	sediments.
Activity #10 - Equipment	
Activity-specific PDCs for	
equipment:	A10.1 Equipment will only be used for its primary/intended purpose.
	A10.2 All equipment will be checked daily for leaks; all projects will have.
	at a minimum. 1 spill kit readily available at all times.
	A10.3 Equipment will not be used until leaks, or other maintenance
	issues are renaired or new equinment is brought in for replacement
	A10.4 To the maximum extent practicable, all equipment maintenance
	and other work that may release pollutante /tayicante will accur in
	and other work that may release politicants/toxicants will occur in
	contained maintenance areas at least 500 feet (preferred) from any
	water body and be outside of active stream channels, outside of any
	tidal areas, and away from ditches or channels that enter flowing waters.
	A10.5 Heavy equipment such as excavators, cranes, and buildozers will
	not be located in the water to conduct work; buckets or extensions may
	reach into the water from atop the bank/platform/trestle to conduct
	work.
	A10.6 Drilling equipment, such as low ground bearing pressure tracked
	rigs, may be used in-water, but not in the main channel of streams,
	creeks, or rivers, and must be in-water for the least amount of time
	necessary to complete work.
	A10.7 Vessels shall operate at "no wake/idle" speeds.
	A10.8 The maximum speed equipment and items can be lowered into
	the water will be no great than 60 feet/minute at times of the year when
	sturgeon or sea turtles may be present.
	A10.8.1 Extreme care will be taken to avoid striking individuals when
	lowering equipment below the water line (and into/onto the bottom).
	Equipment and materials include, but are not limited to: excavator
	buckets, piles, spuds, casings, etc.
	A10.0 Snudding will genur, grouided all other DDCs are adhered to
	A10.9 Spudding will occur, provided all other PDCs are adhered to.
Critical Habitat-specific PDCs:	
	A10.10 Heavy equipment or arilling equipment is not authorized in
	(below the water line) Atlantic Sturgeon critical habitat, where the PBFs
	lare present. Equipment shall only be positioned on barges, temporary fill
	(rip rap pads), temporary work trestles, existing bridges, or in other
	upland areas.

	A10.11 To the maximum extent practicable, barge grounding will be avoided in all Atlantic Sturgeon critical habitat areas and will be limited to 30 days for a given location. Barge grounding is not authorized in Atlantic Sturgeon critical habitat, where the following PBFs are present: • Suitable hard bottom substrate (e.g., rock, cobble, gravel, limestone, boulder, etc.) in low salinity waters (i.e., 0.0-0.5 parts per thousand range [npt]) for settlement of fertilized eggs and refuge, growth, and
	development of early life stages.
4.	1.2 Specific Transportation Project Types
Project Type #2 - New Br	idge, Bridge Replacement, and Bridge Widening; New Piers and
P2.3 Bridge Replacements	
Project-specific PDCs for new	P2.3.1 Bridge replacements on existing or parallel alignments are
bridges and piers,	authorized, provided the original/existing structure is completely
replacement/relocation piers,	removed and the projects follow the PDCs outlined in Section 5.2
replacement bridges, and bridge	("Noise") below and Appendix A, and all other relevant PDCs, including
widening projects:	P2.1.2.
	P2.3.1 Bridge replacements on existing or parallel alignments that span
	the waterbody and remove all old/existing structures from the waterway
	are authorized.
	P2.3.3 Replacement bridges will not allow fishing in areas where
	swimming sea turtles are known to occur (i.e. the salt/freshwater
	interface); "no fishing," "fishing prohibited," or "It is illegal to fish here"
	signs will be used.
	P2.3.4 Replacement bridges will generally be the same size/shape as the original/existing bridges.
	P2.3.4.1 Increases in length and height from original/existing bridges are
	authorized; decreases in height are not authorized.
	P2.3.4.2 Increases of up to 100% of the original width is authorized. For
	example, if the original bridge is 28 feet wide, the replacement bridge
	could be up to 56 feet wide.
P2.5 Bottom substrate/habitat	
impacts	
	P2.5.1 Impacts from piles/columns/footings and other substructure
	components of bridges and piers in the bottom substrate/habitat will be
	limited to 200 ft2 (0.004 acre) or less for any bridge or pier project. This
	is the total impact of newly installed, constructed or cast-in-place
	structures, not measured as the NET impact area (e.g., area of new
	structures minus the area of old structures that will be removed).
Critical Habitat-specific PDCs:	
	P2.7 Bridge/pier replacements within the same footprint of the original/existing structure are authorized. Increases in impact area of piles/columns/footings from the originally authorized structures are not authorized. [see 2.5.1]

Cultural Resources

Cultural Resources Project Scree	ening Form
File Number:PIN:40306Route:SC 4Project Name:SC 4 (Wagener Rd) over South Fork Edisto River Bridge Replacement	County: Aiken
Type 1: Resurfacing, installation of fencing, signs, pavement markings, traffic signals, passenger shelters, railroad warning devices, installation of rumble strips, and landscaping	Project Type 2
Type 2: Bridge replacements on alignment, construction of bicycle/pedestrian facilities, and intersection improvements	
Type 3: Projects that do not fall into Type 1 and Type 2 categories (e.g. road widening)	
Comments This project will replace the bridge carrying SC 4 over the South Fork Ed	listo River. The area of direct effects

(ADE) for archaeological resources includes a corridor of 1000 feet from either end of the bridge and 100 feet from centerline on either side of SC 4. The area of potential effect for architectural resources (APE) extends 300 feet from the ADE. Background review indicated that the southern side of SC 4 was previously surveyed in 2005 by New South Associates. No previously recorded cultural resources are located in the project area. However, the current bridge carrying SC 4 over the South Fork Edisto River (Asset Number 2639) was noted in the SCDOT Historic Bridge Survey. The majority of soils within the ADE are mapped as poorly or very poorly drained, with more well drained soils located at either end of the ADE. A cultural resources survey of the project area was conducted on January 7, 2021 to investigate the northern side of SC 4. The survey consisted of pedestrian reconnaissance of the entire study area augmented by the excavation of shovel test pits (STPs). STPs were not excavated in area of evident ground disturbance or areas inundated with water. At the time of investigation, much of the ADE was flooded. A total of 22 STP locations were investigated, 11 of which were not excavated due to inundation or ground disturbance. One resource was identified. SHPO Site No. #3544 is the current bridge carrying SC-4 over the river. The bridge is a 24-span steel girder/beam structure with a concrete cast-in-place deck that was built in 1958. It is recommended as not eligible for the National Register of Historic Places. No historic properties will be affected. No additional cultural resources investigations are recommended.

Effect Determination:

No Historic Properties Affected

*SHPO consultation is required for all Type 3 projects and any project with a No Adverse or Adverse Effect Determination.

This screening form was developed to satisfy documentation requirements for Type I and Type II projects under a Programmatic Agreement between the Federal Highway Administration, the South Carolina State Historic Preservation Office, the US Army Corps of Engineers, and the South Carolina Department of Transportation. For Type I and Type II projects that have no effect on historic properties, the completion of this screening form with supporting documentation (e.g. ArchSite Map) provides evidence of FHWA and SCDOT's compliance with Section 106 of the National Historic Preservation Act.

Prepared by:	:
--------------	---

Rebecca Shepherd

Review Date:

1/11/2021



ARCHAEOLOGICAL FIELD REPORT NEW SOUTH ASSOCIATES, INC.

1.5

TITLE:Cultural Resources Survey of S.C. 4/302 Bridge Approaches over the South ForkEdisto, Aiken County, South CarolinaDATE OF RESEARCH:January 19-20, 2005ARCHAEOLOGIST:Heather MauldinCOUNTY:AikenSouth Edisto RiverF. A. No.:BRT-BR02(009)File No.:02.127BPINS:26432 and 31552

DESCRIPTION: The Department proposes to replace two bridges located on S.C. 4/302. The project corridor is located 1.5 miles south of SC302. The first bridge, ID number SN 024000400200, is situated over the South Fork Edisto River and is located approximately 10 miles east of the city of Aiken. The existing 601-foot x 28-foot bridge was constructed in 1958, and is a steel continuous stringer type structure. The replacement bridge will be a reinforced concrete flat slab and prestressed concrete Type III beam bridge 600 feet in length and having a 44-foot clear roadway width. The new bridge is to be constructed approximately 45 feet downstream of the existing bridge. The second bridge to be replaced is ID number SN 024000400300, situated over Cedar Creek just east of bridge SN 024000400200. Currently the bridge over Cedar Creek is a concrete tee beam type, originally built in 1932. This replacement bridge will also be constructed approximately 45 feet downstream of the existing overpass. The new bridge will be a modern reinforced concrete flat slab and prestressed concrete Type III bridge with a 44-foot clear roadway width and a length of 120 feet. Both bridges will be supported on cast in place reinforced concrete bent caps with prestressed concrete piles. The improvement also includes a 24-foot approach roadway section in order to accommodate 2 feet of paved shoulder, 8 feet of grassed shoulder, guardrail placement, approach slabs, and surfacing work in order to tie the new construction to the existing roadway. The survey corridor is 1.449 miles in length.

LOCATION: The project corridor is located 10 miles east of the city of Aiken.

USGS QUADRANGLE: Oakwood	<u>DATE</u> : 1999	<u>SCALE</u> : 7.5'
<u>UTM ZONE</u> : 17	<u>EASTING</u> : 452248	NORTHING: 3715490

<u>ENVIRONMENTAL SETTING</u>: The project area is mostly mixed forest, wetlands, and sparse residential and agricultural areas. Vegetation also includes shrubs, grasses, and roadside weeds. Several former mill ponds were identified north of the survey corridor.

<u>NEAREST RIVER/STREAM AND DISTANCE</u>: The nearest rivers/streams are Cedar Creek and the South Fork Edisto River. The project corridor directly crosses each waterway.

<u>SOIL TYPE</u>: The project area falls within two major soil formation areas. These are the Troup-Lakeland-Fuquay and Vaucluse-Ailey-Troup formations. Both formations are described as welldrained, sandy soils that have loamy subsoil and may include a dense brittle layer in the subsoil. Specific soil types encountered within the project area are as follows:

Troup Sand, 6 to 10 percent slope. Troup Sand, 0 to 6 percent slope. Vaucluse-Ailey complex, 6 to 15 percent slopes. Fuquay sand, 2 to 6 percent slopes. Dasher Mucky Peat. Johnson Mucky Loam. Ogeechee Sandy Loam. Orangeburg Loamy Sand, 2 to 6 percent slope.

REFERENCE FOR SOILS INFORMATION:

Rodgers, Vergil A/1983/Soil Survey of Aiken County, South Carolina. USDA, Soil Conservation Service, Washington, D. C.

<u>GROUND SURFACE VISIBILITY</u>: 0% 1-25% X 26-50% 51-75% 76-100%

<u>CURRENT VEGETATION</u>: The vegetation in the corridor consists of mixed forest, bushes, briars, and grasses, and wetland plants. Several landscaped areas also comprise the corridor.

INVESTIGATION:

On December 20, 2004 research was conducted at the State Site Files at the South Carolina Institute of Archaeology and Anthropology. No previously recorded archaeological sites were located within a two-mile radius of the project area. Also on December 20, 2004, the National Register of Historic Places (NRHP) files of the South Carolina Department of Archives and History were searched for previously identified sites using the Arcview program. Eight historic sites were located within a two-mile radius of the project area.

An intensive archaeological survey was conducted on January 20, 2005. One transect was walked at approximately 50 feet south of the existing centerline for the length of the survey corridor. As the bridges and connecting roadway were to be relocated south of the existing roadway, a second transect was deemed unnecessary, as it would have been located beneath the current paved road. A total of 86 shovel tests were excavated in the project corridor, each at 30-meter (100-foot) intervals when conditions warranted. These tests showed that the local subsoil was either a tan occasionally mottled loamy sand, a red occasionally mottled loamy sand or sandy clay, or brown clay.

Eight tests contained dark grey loamy sand to around 15 centimeters above reddish yellow loamy sand; six of these also contained a yellow grey sandy loam layer above the subsoil. Eight additional shovel tests were found to contain tan colored sandy loam as subsoil. Of these seven had a grey loamy sand layer above the subsoil to between 10 and 20 centimeters. The tan subsoil layer occasionally was found to be mottled or contain ferrous concretions. One test produced grey loamy sand to about 5 centimeters, above 15 centimeters of brown loamy sand, 10 additional centimeters of yellow-red loamy sand, and dark red subsoil. Fifteen centimeters of dark grey loamy sand, followed by about 25 additional centimeters of a yellow brown layer

above a brown clay subsoil was found to occur in one shovel test pit. Eleven shovel tests illustrated brown loamy sand above a red to mottled reddish-yellow sandy clay subsoil. The soils in 6 test locations were found disturbed by utilities or road building activities. Forty-two test locations were in wetland areas and were not dug. The remaining 9 tests were conducted at areas in which the ground surface was visible; in these areas the ground was scanned for cultural resources and no subsurface sample was made.

				· · · · · · · · · · · · · · · · · · ·
SITE NO.	DATE	SITE TYPE	ELIGIBILITY	REFERENCE
368-0749	Ca. 1930	Kneece Farm	Not eligible	Preservation
		Clubhouse		Consultants 1988
368-0748	Ca 1935	Kneece Farm	Not eligible	Preservation
		Manager's House		Consultants 1988
368-0274	Ca. 1890	House	Not eligible	Preservation
				Consultants 1988
368-0725	Ca. 1910	Rock Hill Baptist	Not eligible	Preservation
		Church		Consultants 1988
368-0750	Ca. 1920	Kneece's Mill	Eligible	Preservation
				Consultants 1988
368-0765	Ca. 1880	House	Not eligible	Preservation
				Consultants 1988
368-0766	Ca. 1884	Goss Cemetery	Not eligible	Preservation
				Consultants 1988
466-0384	Ca. 1910	House	Not eligible	Preservation
				Consultants 1988

Table 1 . Archaeological and historic sites previously identified in the vicinity of the project area.

The corridor was also surveyed for the presence of historic homes within 400 feet of the road. 35 mm color film photographs were taken of the corridor and any sites or structures that were discovered. GPS coordinates of the corridor were collected. A sketch map showing the location of shovel testing and pedestrian reconnaissance was made to illustrate research of the project corridor.

Bridge number SN 024000400300- Resource ID 2756

The bridge on S.C. 4/302 over Cedar Creek, also known as SN 024000400300, was built originally in 1932. The UTM coordinates for the bridge in Zone 17 are as follows: Easting 452572 Northing 3715792. An architectural survey was undertaken on February 1, 2005, upon which the bridge was identified and photographed using black and white 35 mm film. A South Carolina *Statewide Survey of Historic Properties* form (Site # 2756) was completed.

Bridge 024000400300 is a two-lane, reinforced concrete T-Beam vehicular bridge that provides passage over Cedar Creek on S.C. Rte. 4/302. Constructed in 1932, the bridge is 61 feet in length with a deck width of 30 feet. The substructure consists of a single span of reinforced concrete strengthened by four longitudinal beams. The bridge is supported on both banks of Cedar Creek by an embedded concrete abutment that features retaining wing walls. No additional supports exist. The deck is concrete overlain with asphalt and includes one centrally located drain hole. Solid concrete balustrades, approximately 3 feet high, run the full length of the bridge and are topped with a simple ornamental cap. Galvanized guardrails extend from both ends of the south balustrade and from the northeast end of the north balustrade. A driveway on the southwest end of the north balustrade prevents a guardrail in this location.

It was the only bridge designed for Aiken County between October 1931 and September 1932 according to the South Carolina State Highway Department's Annual Report (December 31, 1929 to June 30, 1938). The Cedar Creek Bridge is a good representative example of a small reinforced concrete T-Beam bridge. However, SN 024000400300 has been determined not eligible for listing on the NRHP due to the considerable number of similar resources of this kind in the state.

Kneece's Mill

In 1988 Preservation Consultants conducted a county-wide survey of historic structures and sites located in Aiken county. As part of this survey, Kneece's mill was identified as eligible for listing on the NRHP and is recorded as ID number 368-0750. This mill reportedly dates to ca. 1930. No standing architecture or surface evidence of the structure's exact placement was identified by our investigations, however a series of three probable mill related ponds exists west of Cedar Creek and north of S.C. 72. This area seems to be the former mill location, and was photographed (see attached). No shovel testing was conducted at the area, due to the wetland situation. As the replacement bridge is to built 45 feet south of the current road location, construction activities should be able to successfully avoid the site location.

Kneece Farm Manager's House

An additional previously documented historic structure near the project corridor is the former Kneece farm manager's house. This structure was also documented by the Preservation Consultants 1988 survey of Aiken County. The house reportedly dates to ca. 1935, and was given the ID number 368-0748. The structure is recommended ineligible for listing on the NRHP. The structure's distance from the road should prohibit any impact from the new right of way.

REMARKS AND RECOMMENDATIONS.

No previously unrecorded archaeological sites were identified along the project corridor. Two previously recorded historic structures were listed as along the project corridor, one of which as recommended eligible for listing on the NRHP. The Cedar Creek bridge (SN 024000400300) although built in 1932 does not warrant consideration of listing on the NRHP, as it is not an exceptional example of its type. Both previously recorded historic sites (368-0750 and 368-0748) should not be directly impacted by proposed improvements. As such, no further cultural resource study of the corridor is recommended.

<u>SIGNATURE</u>:

DATE:

REFERENCES CITED

Rodgers, Vergil A

-

1983 Survey of Aiken County, South Carolina. USDA, Soil Conservation Service, Washington, D. C.

Preservation Consultants

1988 Architectural Survey of Aiken County, South Carolina.

Figure 1 Project Location and Previously Recorded Sites



Source: USGS 7.5' Quadrangles, Oakwood and Kitchens Mill

Figure 2 Project Location on County Map



Source: Aiken County Road Map



> Figure 3 Plan View of Project and STP Locations and Previously Recorded Sites

Wetlands/Water Quality/Floodplains



Watershed and Water Quality Information

General Information

Applicant Name: SCDOT

Address: 107 FLOWING WELL RD, WAGENER, SC, 29164 MS4 Designation: Not in designated area

Within Coastal Critical Area: No

Waterbody Name: SOUTH FORK EDISTO RIVER

Permit Type: MS4

Latitude/Longitude: 33.576940 / -81.516087

Monitoring Station: E-585 Water Classification (Provisional): FW Entered Waterbody Name:

Parameter Description

NH3N	Ammonia	CD	Cadmium	CR
CU	Copper	HG	Mercury	NI
PB	Lead	ZN	Zinc	DO
PH	рН	TURBIDITY	Turbidity	ECC
FC	Fecal Coliform (Shellfish)	BIO	Macroinvertebrates (Bio)	TP
TN	(Lakes) Nitrogen	CHLA	(Lakes) Chlorophyll a	ENT
HGF	Mercury (Fish Tissue)	PCB	PCB (Fish)	

Chromium Nickel Dissolved Oxygen DLI Escherichia coli (Freshwaters) (Lakes) Phosphorus TERO Enterococcus (Coastal Waters)

Impaired Status (downstream sites)

Station	NH3N	CD	CR	CU	HG	NI	PB	ZN	DO	PH	TURBIDITY	ECOLI	FC	BIO	TP	ΤN	CHLA	ENTERO	HGF	PCB
E-585	Х	Х	Х	Х	Ν	Χ	Х	Х	Х	Х	Х	Х	Х	Х	Х	Х	Х	Х	Х	Х
E-114	F	F	F	F	Α	F	F	F	F	F	F	WnTN	Х	Х	Х	Х	Х	Х	Х	Х
RS-14209	Α	Α	Α	Α	Α	Α	Α	Α	Α	Α	Α	Α	Х	Х	Х	Х	Х	Х	Х	Х
E-600	Α	Α	Α	Α	Α	Α	Α	Α	Α	Α	Α	Α	Х	Х	Х	Х	Х	Х	Х	X

F = Standards full supported N = Standards not supported A = Assessed at upstream station X = Parameter not assessed at station WnTN = Within TMDL, parameter not supported InTN = In TMDL, parameter not supported WnTF = Within TMDL, parameter full supported InTF = In TMDL, parameter full supported

Parameters to be addressed (those not supporting standards)

HG - Mercury

ECOLI - Escherichia coli (Freshwaters)

Fish Consumption Advisory

Waters of Concern (WOC)

TMDL Information - TMDL Parameters to be addressed

In TMDL Watershed: Yes

TMDL Site: E-114 TMDL Parameter: Fecal

TMDL Report No: 9D21-11

Report Date: December 23, 2020

TMDL Document Link: https://www.scdhec.gov/sites/default/files/docs/HomeAndEnvironment/Docs/tmdl_mlEdisto.pdf

Date: 12/22/20
PERMIT DETERMINATION
FROM Will McGoldrick COMPANY SCDOT
CONTACT INFO (phone and/or email) 803-737-1326; mcgoldriwr@scdot.org
SCDOT PROJECT ENGINEER Brad Reynolds
TO Will McGoldrick - Design Build Coordinator
Project Description SC 4 Emergency Bridge Replacement
Route or Road No. SC 4 County Aiken
CONST. PIN P040306 OTHER PINS or STRUCTURE #
RESPONSE:
OIt has been determined that no permits are required because:
 The following permit(s) is/are necessary: (Please check which type(s) of permit the project will need) USACE Permit
303(d) listed $Ono Oyes, for * HG (WQMS E-585)$
TMDL developed no yes, for * Fecal (WQMS E-114) *List all that apply using the SCDHEC abbreviations
Comments:
The determination above was based on the most recently available information at the time. This

The determination above was based on the most recently available information at the time. This is a preliminary determination and is subject to change if the design of the project is modified.

Will McGoldrick Digitally signed by Will McGoldrick Date: 2021.01.08 08:12:14 -05'00'

Biologist, SCDOT/Consultant




National Flood Hazard Layer FIRMette



Legend





South Carolina Department of Transportation Location and Hydraulic Design of Encroachments on Floodplains Checklist

23 CFR 650, this regulation shall apply to all encroachments and to all actions which affect base floodplains, except for repairs made with emergency funds. Note: These studies shall be summarized in the environmental review documents prepared pursuant to 23 CFR 771.

I. PROJECT DESCRIPTION

The project consists of replacing a structurally deficient bridge over the South Forth Edisto River in Aiken county. The bridge will be replaced on alignment with a close and detour route implemented.

- A. Narrative Describing Purpose and Need for Project
 - a. Relevant Project History:
 - b. General Project Description and Nature of Work (attach Location and Project Map):
 - c. Major Issues and Concerns:

Recent bridge inspections determined that the steel bridge girders had become detached from the deteriorated timber bent caps and that the bridge was unsafe for public travel. The bridge was closed near the beginning of December 2020 to all traffic. The bridge is located in Aiken County on SC 4. Due to the poor substructure condition, the bridge was determined to be an emergency replacement and assigned to Design-Build for delivery.

- B. Are there any floodplain(s) regulated by FEMA located in the project area? Yes⊠ No⊡
- C. Will the placing of fill occur within a 100-year floodplain? Yes \boxtimes No \square

D. Will the existing profile grade be raised within the floodplain?

Yes. The grade will be raised approximately 2-4 feet to account for difference in superstructure depth, while maintaining or slightly increasing the existing low chord elevation.

E. If applicable, please discuss the practicability of alternatives to any longitudinal encroachments.

Lengthening the bridge to span the entire floodplain would significantly increase the downstream floodplain and result in a conditional letter of map revision (cLMR). Offalignment alternatives were considered but ruled out due to significant increases in wetland impacts, as well the need to avoid impact to an existing pond and overflow bridge structure to the east of the project.

- F. Please include a discussion of the following: commensurate with the significance of the risk or environmental impact for all alternatives containing encroachments and those actions which would support base floodplain development:
 - a. What are the risks associated with implementation of the action?

Little to none in the overall system. The proposed bridge will not significantly alter backwater conditions and design high-water elevations. The minimal amount of added fill will be an insignificant percentage of the overall available floodplain available for storage.

b. What are the impacts on the natural and beneficial floodplain values?

Little to none. Impacts to the overall available floodplain will be near or at zero.

c. What measures were used to minimize floodplain impacts associated with the action?

Bridge spans will be lengthened thereby reducing the amount of piles to be located in the floodplain which will allow more area for surface flows to flow unimpeded. This will also reduce debris accumulation. Replacing on-alignment restricts the fill impacts to a minimal amount on either side of the existing approach embankments. d. Were any measures used to restore and preserve the natural and beneficial floodplain values impacted by the action?

Yes, reduced bents in the floodplain through longer spans. Spanning the river channel. Slightly increasing the bridge length. Maintaining or slightly increasing the existing freeboard and vertical clearance.

G. Please discuss the practicability of alternatives to any significant encroachments or any support of incompatible floodplain development.

There are no significant encroachments and the project will not support or encourage further development in the floodplain. Existing roadway geometry is not conducive to off-alignement replacement.

H. Were local, state, and federal water resources and floodplain management agencies consulted to determine if the proposed highway action is consistent with existing watershed and floodplain management programs and to obtain current information on development and proposed actions in the affected? Please include agency documentation.

Not at this time. Once a final design is developed by the Design-Builder, they will be required to coordinate with the local NFIP personnel to ensure compliance with local and federal regulations.

Maria Ott

01/06/2021

SCDOT Hydraulic Engineer

Date

US Coast Guard Coordination

From:	Overton, Randall D CIV
To:	Belcher, Jeffery - FHWA
Cc:	McGoldrick, Will; D07-DG-DISTRICTSTAFF-DPB
Subject:	RE: [Non-DoD Source] FHWA-South Carolina: USCG Bridge Permit Exemption SC 4 over S. Fork of Edisto River
	Emergency Bridge Replacement
Date:	Friday, January 8, 2021 8:06:44 AM
Attachments:	SC4 USCG Exemption Request printed.pdf

*** This is an EXTERNAL email. Please do not click on a link or open any attachments unless you are confident it is from a trusted source. ***

Shane,

I (the Coast Guard) concurs with your determination that the SC 4 Bridge across the South Fork of the Edisto River is exempt from Coast Guard bridge permitting requirements; a Coast Guard bridge permit will not be required for the replacement of the subject bridge.

Thank you – v/r, Randy

Randall Overton, M.P.A

Director, District Bridge Program Coast Guard Seventh District 909 SE 1st Ave Suite 432 Miami, Fl 33131 (305) 205-0795 Cell (305) 415-6736 Office

From: Belcher, Jeffrey (FHWA) <Jeffrey.Belcher@dot.gov>
Sent: Tuesday, January 5, 2021 4:22 PM
To: Overton, Randall D CIV <Randall.D.Overton@uscg.mil>
Cc: McGoldrick, Will <McGoldriWR@scdot.org>
Subject: [Non-DoD Source] FHWA-South Carolina: USCG Bridge Permit Exemption SC 4 over S. Fork of Edisto River Emergency Bridge Replacement

Randall,

Attached is a permit exemption form for your review/concurrence. FHWA feels an exemption for the subject project is appropriate. The bridge is currently closed to traffic and is proposed for emergency replacement due to structural deficiencies. Boat traffic is limited to small craft (canoes, kayaks, john boats). Any questions or concerns, please let me know.

Much thanks,

J. Shane Belcher Lead Environmental Specialist Federal Highway Administration 1835 Assembly Street, Suite 1270 Columbia, SC 29201 Phone: 803-253-3187

The content of this email is confidential and intended for the recipient specified in message only.



FHWA South Carolina Division

U.S. Coast Guard Permit Exclusion Request Checklist

STATES OF P										
State File #	P040306	Fed Project #	PIN		Date	12/22/20	County	/ Aiken		
Project Desc	ription SC 4 Emerge	ency Bridge Replacen	ient							
Tidal or Non	Tidal or Non-Tidal Contact Person Will McGoldrick Phone Number 803-737-1326									
								a		

Form Purpose: The FHWA has the responsibility under 23 U.S.C. 144(h) to determine that a USCG permit is not required for bridge construction. This determination shall be made at an early stage of project development so that any necessary coordination can be accomplished during environmental processing (23 CFR Part 650.805).

Form Instructions: This checklist should be completed when requesting a Title 23 Coast Guard Permit Exclusion. The exclusion request should be submitted prior to completion of the NEPA process. When an exclusion is requested SCDOT should send a letter to FHWA, addressed to the Division Administrator requesting such, with the appropriate information listed below. If the FHWA Structural Engineer agrees that an exclusion is appropriate, a letter will be sent to the U.S. Coast Guard indicating that a permit is not required. The letter will allow 30 days for a U.S. Coast Guard rebuttal.

I. For Non-Tidal Waterways:

The following condition must be met to obtain a Title 23 Coast Guard Permit Exclusion. A "no" response will result in the need for a USCG Permit.

1.	If the non-tidal waterway is navigable, is not currently utilized by commercial or recreational vessels greater than 21 feet in length, and will not be used as such, once improvements (increased vertical and/or horizontal clearance) have been constructed, a USCG permit is not required.	🔀 Yes	🗌 No
Inforn This d	nation required by FHWA for non-tidal waterways to issue a Title 23 Permit Exclusion. ata will need to be provided with exclusion request.	Include requ	d with lest
1.	Location Map		<
2.	Photo of existing bridge/location from the waterway	\triangleright	3
3.	Bridge profile at crossing	\triangleright	3
4.	Depth of water at normal pool	Σ	3
5.	Vertical clearance at normal pool	Σ	3
6.	Horizontal clearance at normal pool		<
7.	Type of vessel traffic (commercial or recreational) and whether there are vessels > 21 feet utilizing the waterway.		3

II. For Tidal Waterways:

The following condition must be met to obtain a Title 23 Coast Guard Permit Exclusion. A "no" response will result in the need for a USCG Permit.

1.	If the tidal waterway is navigable, is not currently utilized by commercial or recreational vessels greater than 21 feet in length, and will not be used as such, once improvements (increased vertical and/or horizontal clearance) have been constructed, a USCG permit is not required.	🗌 Yes	🗌 No
Inforn This d	nation required by FHWA for tidal waterways to issue a Title 23 Permit Exclusion. ata will need to be provided with exclusion request.	Include requ	d with lest
1.	Location Map		
2.	Photo of existing bridge/location from the waterway		
3.	Bridge profile at crossing	Γ	
4.	Depth of water at high and low tides	Γ	
5.	Vertical clearance at high and low tides	Γ	
6.	Horizontal clearance at high and low tides	C	
7.	Type of vessel traffic (commercial or recreational) and whether there are vessels > 21 feet utilizing the waterway.	E	

Vessel traffic in this location of the South Fork Edisto River is recreational and is less than 21' in length. Most vessels are for fishing or site seeing and consists of canoes, kayaks, or john boats.

SC 4 Location Map

Write a description for your map.

26

Aiken

118

303)

Feature 1
SC 4 bridge

389 Perry

Sall

14

Wagener

270

7 mi

113

39

SC 4 bridge SC 4 bridge

394

4

-Wagener-Roo2

Montmorenci

78

Google Earth

(192)

@2020 Google



Salley-Rd-

Windsor

212

Surrey Race Re-

Six Indian-Frail

	b40306bp1.dgn				
		$\langle \rangle$			
	00+		00+		
	514	\times	515		
			Approximate T	oe of Fill	
			MGS GL	uardrail (Typ.)——	4'-0" Slope Flur accordance with
					/19-920-00 (Typ.
<u>. ń</u>	<u>à à à à à à</u>	<u>i i i i i i</u> 13'-9"			<u>ả ở ở ở ở ở</u>
	To Aiken	Shoulder —		¢ Survey SC 4 & (bridge
		←	, ' LD , ' LD , ' L , '	B°_22′_00″_E	· · · · · · · · · · · · · · · · · · ·
		→	- ane		
		13′-9″			
<u>p</u>	ō û û û û û	, , , , , , , , , , , , , , , , , , ,	r <u> </u>	0 0 0 0 0 0	<u> </u>
				Edae	of Pavement (Typ.)-
		Existing Powe	er Pole (Typ.)		MTBBC3 S
					Тур. еас
Notor	ו				
Place	, Bridae End Ripran	(not shown) in accor	dance with Standard	Drawipa 801-105-00	
Desic	p-Build Team to de	termine number and lo	cation of deck drain	as a second seco	
Hydro	ploav data to be de	termined.		•	
Found	dation dependant on	Final Bridge Geotech	nical Report.		
	Benchmark #4				
	Nail in 10" Pine Sta. 508+93.44				
320	65.82' Right Elev. = 263.92			<u> </u>	
				5 + 45 5 63 1 - 5 63	
300				2 + + + + + + + + + + + + + + + + + + +	
		51			
280		240 240		- 0 0 • − • − •	Finished Grade
		VP(+ 0.95% + 0.	31%
000					
260				Existing	j Ground @ ¢ Survey S
240					
220					
_220					
200					
100					
180					
160					
1 4 0					
<u>140</u> 51	4+00 +20	+40 +60	+80 515+00	+20 +40	+60 +80 5



· · · · · · · · · · · · · · · · · · ·			-41.	ч с S	1.9	Elev. = 2	73.023	0.0						· · · · · · · · · · · · · · · · · · ·	
· · · · · · · · · · · · · · · · · · ·			216+		72.95 dge 91.00 73.01			007 • 02 • • •				00 00 1 3 2 0 0 0 0 0 0 0 0 0 0 0 0 0			
			•	51.6+	5 16 1 1 Br 1			t ∾ - 11 - Ω				518+			
		· · · · · · · · · · · ·		S+0.	1										
· · · · · ·	· · · · · · · · · · · · · · · · · · ·	· · · · · · · · · · · · · · · · · · ·													
							7777777								
;4:								777					· · · · · · · · · · ·		
					• <u> </u>	Riprap			24	1" Squar	-e				
						(See Road PI	ans)—		Pr P	recast (iles (Ty	Concrete (p.)				
			BENT	' NUI				2				3			
· · ·	· · · · · · · · · · · ·	· · · · · · · · · ·													
					SECTI	ION A	LON	GY	S	UR	VEY	s (74	f	
· · · · · · · · · · · · · · · · · · ·	· · · · · · · · · · · · · · · · · · ·	· · · · · · · · · · · · · · · · · · ·											· · · · · · · · · · · · · · · · · · ·		
· · · · · · · · · · · · · · · · · · ·						Legend:									· · · · ·
						F	= Excavati = Fixed b	e natche earing	eq ur ec	J (See H					· · · · ·
· · · · · · · · · · · · · · · · · · ·							= Expansi = Inteara	on beari bent	ng						
6+00	+2	°0	+40	+60	+80	517+00 +2	20 +	40	+60	+1	30 5	518+00	+2	0 +	-40



+2	20	+4	+0 +	60 +8	30	522+00	+20	+4	10	+60	+{	30 52	3+00	+20 +	40 +60
· · · · · · · · · · · · · · · · · · ·			I = Intec	pral bent											
•	· · · · · ·		E = Expar	nsion beari	ng										
 			$\mathbf{X} = Excav$	ate hatche	d area	See Road	IPlans)								
 		egen	d:										· · · · · · · · · · · · · · · · · · ·		
			······································					· · · · · · · · · · · · · · · · · · ·		· · · · · · · · · · · · · · · · · · ·	· · · · · · · · · · · · · · · · · · ·				
\mathbb{I}	ON	V	ALO]	NG 4	s I	JRVI	EY	SC	4						
• • • • •															
 		1								10			· · · · · · · · · · · · · · · · · · ·	- BENT	NUMBER
 			Piles	з (Тур.)											
			24″S Prece	Square st Concret	e · · · · · · ·			· · · · · · · · · · · · · · · · · · ·				ee Road P	ans)		
 											_ ₽;	Drab		2 : 1 <u> </u>	
•											<u>[</u>]]77.	and a standard and a		-0"Berm	
 	F C	. F			F C	F						TIT		Ī	
(
 	ent (1.52				ent (1.52'			· · · · · · · · · · · · · · · · · · ·	ent (•	Elev.	= 274.965	· · · · · · · · · · · · · · · · · · ·	d ADF • 52 ev	2C S+
	274.				9 +91. 				-+56. -+56.	2 	End o Sta. S	f Bridge 523+11.00		1.275.	22
	00 400				8 80 200									• • 00 S I C	2 +2 5
 								· · · · · · · · · · · · · · · · · · ·			y End Sta. Elev.	523+09.67 = 274.961		q	• 02
•••			<u> </u>				62 -0	Span y			55 -(Pact 11			
A'A	<u>SHTO</u>	Туре	II Prestr	essed Concr	ete Bea	ms)						·····	· · · · · · · · · · · · · · · · · · ·	Approach Slab	· · · · · · · · · · · · · · · · · · ·
Br	idge	(out	to.out.)		· · · · · · · · · · · · · · · · · · ·					· · · · · · · · · · · · · · · · · · ·	· · · · · · · · · · · · · · · · · · ·			201 -0"	

	BRIDGE PLANS ID	SHEET NO.
	P040306-B01	BP2
525		
Approximate Toe of Fill		
← 4′-0″ Slope Flume & Riprap pad in		
accordance with Standard Drawing 719-920-00 (Typ. each corner) MGS Guardrail (Typ).)	
	<u>. ἀ ἀ ἀ</u>	<u>à à</u>
Shoulder		
int N 48° 22′ 00″ E ♀ ↓ 5		
	To Springfiel	
		-
		<u> </u>
Edge of Pavement (Typ.)		
-MTRBC3 Stiffness Transition.		
Typ. each corner Existing Power Pole (Typ.)—	•	
Notes:		
Place Bridge End Riprap (not shown) in accordance with Standard Dr	awing 804-105-	00.
Design-Build Team to determine number and location of deck drains.		
Hydrology data to be determined.		
Foundation dependant on Final Bridge Geotechnical Report.		
Bench	mark #6 in 18″ Pine	
Sta. 73.89	529+96.71 ' Riaht	
	= 259.44	320
<u>9</u> +1-5 2,755		300
Einished Grade		
		280
$+ 0.51 \frac{1}{2} - \frac{1.68\%}{2}$		
Existing Ground @ ¢ Survey SC 4		260
		200
	· · · · · · · · · · · · · · · · · · ·	240
		220
		200
+20 +40 +60 +80 525+00 +20	+40	
SOUTH CAROLINA		
REV. DEPARTMENT OF TRANSPOR		180
FOR REV. BRIDGE PLAN & PRO	FILE	
INFORMATION REVIEWED REPLACE BRIDGE OV		160
ONLY OUAN. SOUTH EDISTO RIVI	SK –	
$\begin{array}{c ccccccccccccccccccccccccccccccccccc$		
BY CHK. DATE AIKEN S(C 4 / SC 302	140







Bridge Inspection Reports and Information

SCDOT BRIDGE INSPECTION FORM

(008) BRIDGE ID:	0240000400200			(005) ROUTE:		AIKEN SC-4	1			
(420) ASSET NO:	2639			(006) CROSSIN	G:	S. EDISTO	RIVER			
(419) RAMP NO:				(009) LOCATIO	N:	10 MI E OF	AIKEN			
(026) FUNCTIONAL CLASS:	3			(016) LAT:	33d 34	m 36.39s		(017) LON	l: 81d 30m 59.4	7s
			GEN	ERAL BRIDGE DA	ATA					
	EXISTING	REVISED					Ε>	KISTING	R	EVISED
(027) Year Built	1932			(042) Type Serv	; On(A) Und(B)	1	5		
(106) Year Recon	1958			(028) Lanes; On	ı(A) Un	d(B)	2	C		
(031) Design Load	2			(107) Deck Strue	ct			1		
(36A) Railings	0			(108) Wear Surf	/Memb	rane/Prot	6	8 8		
(36B) Transitions	0						MAT	-SUP-SUE	MAT	I-SUP-SUB
(36C) Appr Guard	1			(043) Main Origi	nal (A)		4	2 7		
(36D) Appr Guard End	1			Main Reco	onst (B)		4	02 7		
(037) History	5			(044) Appr Orgir	nal (A)		0	00 0		
(319) Last Paint Date				Appr Reco	nst (B)					
			G	EOMETRIC DATA	4					
	EXISTING	REVISED					E>	KISTING	R	EVISED
(032) Appr Rdway	28						FT	11	I FT	IN
(033) Bridge Median	0			(053) Vert Clr At	bove D	eck	99	99	9	
(034) Skew	0			(54A) Vert Clear	Ref			Ν		
(035) Flared	0			(54B) Vert Clear	Right		0	C	0	0
(045) # Main Spans	24			(54C) Vert Clear	r Left		0	C	0	0
(046) # Appr Spans	0			(10A) Great Min	Clr Ov	er/Und	99	99	9	
(048) Max Span Lgth	25			(10B) Great Min	Right		99	99	9	
(308) Appr Span Lgth	0			(10C) Great Min	Left		99	99	9	
(049) Struct Length	601									
(47A) Horz Clear Right	28			(55A) Lat Clear	Ref			Ν		
(47B) Horz Clear Left	0			(55B) Lat Clear	Right			0		
(47UA) Horz Clear Right	0	0		(056) Lat Clear I	Left			0		
(47UB) Horz Clear Left	0	0								
(50B) Sidewalk Right	0			(038) Navigation	n Cont			0		
(50A) Sidewalk Left	0			(039) Nav Vert 0	Clear			0		
(051) Curb to Curb	28			(040) Nav Horz	Clear			0		
(052) Deck Out-Out	31			(111) Nav Pier F	Port					
				RATINGS DATA						
	EXISTING	REVISED					Ε>	KISTING	R	EVISED
(58) Deck	5			(041) Traffic Sta	tus			Р		
(59) Super Str	3			(063) Rating Me	thod			2		
(60) Sub Str	3			(064) Operating	Metho	d		45		
(061) Channel	7			(065) Rating Me	thod			2		
(062) Culv Ret	Ν			(066) Inventory I	Rating			30.60		
(071) Water Adeq	7			(411) Date Rate	d		0	6/1988		
(072) Appr Rdway	8			(418) Conditions	During	g Rating	5	4 3		
(113) Scour Critical	5						Freq	Mth/Yea	r Freq	Mth/Year
(067) Structure	3			(091, 090) Routi	ne Insp)	12	02/2020		
(068) Deck Geom	4			(92A, 93A) Fract	ture Cr	itical	Ν			
(069) Underclear	Ν			(92B, 93B) Unde	erwater	Insp	Ν			
(070) Bridge Post	5			(92C, 93C) Spec	cial Ins	p	Y12	08/2019	Y12	08/2020
Inspection Leader: VARTE	ENISIAN, DREW			Reviewed By:	BONNI	ETTE, GERA	D			
Date:				Date:	9/8/202	20				

Bridge Element Group Textual Data

Bridge ID: 02-4-00004-0-02-00

08 Sep 2020

Abutments and/or Headwalls:

N/A

Bents and/or Piers:

O.C. (043A) HAS 4 TIMBER PILES W/ ~12" SQUARE TIMBER CAPS/ R.C. (043B) WIDENED ON BOTH SIDES W/ 1 TIMBER PILE AND TIMBER CAPS W/ SPLICING BOARDS, ALL W/ TIMBER SWAY BRACING/ CAPS:

-TIMBER CAPS HAVE MINOR DETER. THRU-OUT, W/ SEVERAL CAPS HAVE MINOR CRUSHING, AND MOD. TO MAJ. DETER., W/ WORSE ON CAP ENDS AND WIDENED SECTIONS; (~770'-LF) -CAP#2= MINOR FIRE DAMAGE OVER P5+6 (5'-LF);

-CAP#23(LT-SIDE)= SEVERE DECAY W/ SECTION LOSS ALLOWING SETTLEMENT (UP TO 1/4") ON BM#1 SP#23 (I.E. BEARING PLATE IS BENDING DOWN ~1/4");

-CAP#23(RT-SIDE)= CRUSHING + ROTATION UNDER BEAMS #5-6;

-CAP#24= 6' SPLIT @ C/L, ARRESTED W/ BOLTS;

-HEAVY SATURATION THROUGH OUT SUBSTRUCTURE ELEMENTS; PILES:

-137-ORIGINAL INTERIOR BT PILES + 12 ON END BENTS (149 TOTAL); (BT11 P5 WAS REPLACED W/ 2 HELPER PILE W/ H-PILE SUPPORT CAP IN ITS PLACE);

-30 HELPER PILES ARE TYP. DRIVEN AT/NEAR SEVERELY DETERIORATED PILES;

-4 PILES SPLICED W/ METAL COLLARS;

-MINOR TO SOME AREAS OF MOD. DECAY THRU-OUT PILES W/ NUMEROUS AREAS OF SEVERELY CORRODED AND FAILED CONNECTIONS;

-MOST HELPER PILES SHIMS HAVE HEAVY RUST W/ PACT RUST AND SECTION LOSS;

08-28-20 SPECIAL INSPECTION NOTES -SEE MISC SECTION FOR DETAILS;

SEE SKETCH SHEETS FOR FURTHER DETAILS

Bearings:

108-FIXED AND 108 MOVABLE STEEL PLATES/ -MOVABLE PLATES (UNDER OPEN JOINTS) ARE FROZEN WITH TYPICAL HEAVY RUST ON MOST, WITH MANY HAVING SOME LEVEL OF SECTION LOSS; -MINOR RUST TYPICALLY ON FIXED PLATES;

SEE SKETCH SHEETS FOR FURTHER DETAILS ON CAPS AND PILES

Girders/Floor Beams/Stringers and/or Beams:

6-18" STEEL"I"BEAM ON A 2 SPAN CONTINUOUS BEAM DESIGN (I.E. 72 INDIVIDUAL BEAMS AND 144 BEAM ENDS ON ODD # OF BENTS); ACCORDING TO BRIDGE PLANS IT APPEARS THAT THE BEAMS AND DECK ARE ONLY COMPOSITE AT BEAM ENDS/ -DIAPHRAGMS HAVE HAIRLINE CRACKS W/ SMALL TO LARGE SPALLS THROUGHOUT; -SEVERE RUST WITH COMPACTION AND MAJOR TO COMPLETE SECTION LOSS ON NUMEROUS BEAM ENDS; -EVERY BEAM END HAS SOME LEVEL OF DETERIORATION; -BEAMS AT MID-SPAN AND OVER FIXED BENTS (EVEN # BENTS) TYPICALLY HAVE MINOR RUST ON FLANGES THRU-OUT BEAMS;

-BEAMS #2-5 (O.C.) HAVE HEAVY RUST WITH CREVICE COMPACTION B/W BEAM AND DECK WHICH IS CAUSING SEPARATION (1/8" IS TYPICAL)

08-28-20 SPECIAL INSPECTION NOTES -SEE MISC SECTION FOR DETAILS;

SEE SKETCH SHEETS FOR FURTHER DETAILS

Truss Members:

N/A

Expansion Joints:

13-O.C. POURABLE EXPANSION JOINTS (JOINTS ON ODD # BENT), UNABLE TO INSPECT TOP SIDE DUE TO ASPHALT OVERLAY/ -VISIBLE EVIDENCE OF LEAKAGE FROM JOINTS, COMPLETELY FAILED -NO JOINT MATERIAL ON CURB SECTIONS WHICH IS ALLOWING WATER TO GET TO FASCIA BEAM ENDS AND CAPS, AND CAUSING HEAVY SATURATION IN THESE ELEMENTS;

-NO OTHER NOTICEABLE CHANGE

Decks and/or Slabs:

7-11/16" (VARIES) CAST IN PLACE CONCRETE DECK ON OC AND RC WITH APPROX 4" OF ASPHALT OVERLAY, 24 SPANS AT 25'/ SOFFIT: -HAIRLINE AND UP TO ~1/16" TRANSVERSE CRACKS (MOST PROMINENT) UNDER ON DECK SOFFIT, WITH CONNECTING LONGITUDINAL (I.E. MAP CRACKING) THRU-OUT, SPACED @ 6"-1', WITH SOME HAVING LIGHT TO MINOR EFFLORESCENCE(UP TO ~5% IN CS2); -22 CUT-OUTS (FULL DEPTH PATCHING) FOR HELPER PILE INSTALLATIONS (22-3' X 3'(AVG)= 198'-SF IN CS3) -DUE TO COMPACTION RUST BETWEEN BEAMS AND DECK IT MAY BE A POSSIBILITY OF DECK DISTORTION FROM ~5' FROM EACH OPEN JOINT (2015'-SF IN CS3)

WEARING SURFACE: 4" OF ASPHALT OVERLAY (28' X 601')= WIDE CRACKING OVER ODD BENT JOINTS (364'-SF IN CS3);

SEE SKETCH SHEETS FOR FURTHER DETAILS

Curbs:

CONCRETE SAFETY CURB ON BOTH SIDES ACROSS BRIDGE/ -LIGHT ABRASION ON CURB TOPS AND MINOR AT CURB AND GUTTER CORNERS; -CURB REVEAL: BEG LT - 11.25" BEG RT - 11" END LT - 11" END RT - 11.25"

Bridge Railing/Parapets and/or Median Barriers:

36A: CONCRETE RAILING ACROSS BRIDGE; 36B: W-BEAM RAILING WITH TIMBER POSTS ON TRANSITIONS; 36C: W-BEAM GUARDRAIL WITH TIMBER POSTS ON APPROACHES; 36D: FLARED BACK BULL NOSE ON ALL END TREATMENTS;

08-28-20 SPECIAL INSPECTION NOTES -SEE MISC SECTION FOR DETAILS;

SEE SKETCH SHEETS FOR FURTHER DETAILS

Paint Systems:

-COMPLETE FAILURE AT BEAM ENDS (APPROX 3' FROM ENDS=12% OR 1944'-SF); -COMPLETE FAILURE ON BEARINGS; -SOME AREAS ON BEAMS THAT HAVE "LIMITED" TO "NO LONGER EFFECTIVE" AT 4' FROM BEAM ENDS AND OUTSIDE 2 BEAMS (1297'-SF); -MOSTLY EFFECTIVE ON MID SPANS (APPROX 80% or 12962'-SF);

Waterway and Scour:

-RIPRAP AT BOTH ENDS OF BRIDGE AND SIDE SLOPES; -GOOD ALIGNMENT WITH FLOOD PLAIN; -WELL VEGETATED SLOPES AND BANKS BEYOND BRIDGE BUT NO PROTECTION ON CHANNEL BANKS UNDER BRIDGE; -~4'WIDE X 2'DEEP SINK HOLE FORMING @ BENT#7 FROM ACTIVE ARTESIAN WELL;

Fender System:

N/A

Roadway Alignment:

STRAIGHT ALIGNMENT AND NO SPEED REDUCTION NECESSARY;

Traffic Signs:

-BRIDGE END PANELS ON ALL CORNER; -"SOUTH EDISTO RIVER"; -LOCATION ID; -ASSET ID; -AT BRIDGE POSTED SIGNS AND ADVANCED WARNING SIGNS (ALSO WITH ADVANCED TRUCK DETOUR SIGNS ALSO IN PLACE);

Encroachments:

-ONE 4" FIBERGLASS UTILITY ON RIGHT AND ONE 4" FIBERGLASS ON LEFT RUNNING ALONG BEAM FASCIA;

Miscellaneous Notes:

-WEATHER: ~90 AND CLEAR; -WORK REQUEST: DEC-2019 B-FLAG (BEAM SUPPORTS) *08-28-20 SPECIAL INSPECTION FOR BENT #23 SETTLEMENT NOTES* -THIS SPECIAL INSPECTION IS PRIMARILY FOR THE MONITORING OF SETTLEMENT/DETER. ON BENT #23 AND SURROUNDING ELEMENTS. DURING INSPECTION, A SQUEAK WAS NOTICED AT BM4 OF SP22 AT BT23 AND BM2 SP24 AT BT25, WHICH HAD PROGRESSIVE DETER. AND NOTICEABLE DEFLECTION BENT #23 RT-SIDE SETTLEMENT MEASUREMENTS___ -ON RAILING: 8-30-18= JUST LESS THAN 26/32"; 2-15-19= 27/32" 8-20-19= 26/32" 2-14-20= 27/32" (51*D) 8-28-20= 7/8" (90*D) -ON CURB: 2-14-20= (~+)1.40" (51*D) 8-28-20= (~-)1.25" (90*D), *ACCOUNTING FOR THERMAL EXP, THIS MEASUREMENT WOULD BE CLOSE TO 1.43" -SWAY BRACING OUTSIDE CORNER TO TOP OF BEARING PLATE ON CAP BEGINNING: 8-28-20= 17_7/16" *WORK REQUEST: DEC-2019 B-FLAG, DUE TO RAIN FALL, WATER LEVEL AND HIGH WATER TABLE, COVID-19 WORK HAS BEEN SLOWLY PROGRESSING; (E.G. FOOTING DUG BUT FILLED WITH WATER AND FOOTER FORMS AT BRIDGE SITE);

Bridge Element Level Data

08 Sep 2020

					Quantit	ty in Each	Conditio		
Element No	Element Name/Description	<u>Units</u>	<u>Env</u>	Defect	<u>1</u>	<u>2</u>	<u>3</u>	<u>4</u>	Total Qty
107	Steel Open Girder/Beam	feet	3	Yes					
107	Corrosion	feet	3	1000	0	2886	0	720	3606
107	Steel Open Girder/Beam	feet	3	Yes	0	2886	0	720	3606
12	Reinforced Concrete Deck	sq feet	3	Yes					
12	Delamination/Spall/Patched Area	sq feet	3	1080	0	0	198	0	198
12	Exposed Rebar	sq feet	3	1090	0	0	3	0	3
12	Efflorescence/Rust Staining	sq feet	3	1120	0	965	0	0	965
12	Cracking (RC and Other)	sq feet	3	1130	0	15448	25	0	15473
12	Distortion	sq feet	3	1900	0	0	2015	0	2015
12	Reinforced Concrete Deck	sq feet	3	Yes	0	16415	2241	0	18656
228	Timber Pile	each	4	Yes					
228	Connection	each	4	1020	0	0	28	0	28
228	Decay/Section Loss	each	4	1140	0	0	126	27	153
228	Timber Pile	each	4	Yes	0	0	154	27	181
235	Timber Pier Cap	feet	4	Yes					
235	Decay/Section Loss	feet	4	1140	0	736	20	0	756
235	Split/Delamination (Timber)	feet	4	1170	0	0	6	0	6
235	Settlement	feet	4	4000	0	0	3	5	8
235	Damage	feet	4	7000	0	0	5	0	5
235	Timber Pier Cap	feet	4	Yes	0	736	34	5	775
301	Pourable Joint Seal	feet	4	Yes					
301	Leakage	feet	4	2310	0	0	0	39	39
301	Seal Adhesion	feet	4	2320	0	0	0	364	364
301	Pourable Joint Seal	feet	4	Yes	0	0	0	403	403
311	Movable Bearing	each	4	Yes					
311	Corrosion	each	4	1000	0	0	0	108	108
311	Movable Bearing	each	4	Yes	0	0	0	108	108
313	Fixed Bearing	each	4	Yes					
313	Corrosion	each	4	1000	0	72	0	0	72
313	Fixed Bearing	each	4	Yes	0	108	0	0	108
331	Reinforced Concrete Bridge Railing	feet	2	No	1202	0	0	0	1202

510	Wearing Surfaces	sq feet	4	Yes					
510	Crack (Wearing Surface)	sq feet	4	3220	0	0	308	0	308
510	Wearing Surfaces	sq feet	4	Yes	16520	0	308	0	16828
515	Steel Protective Coating	sq feet	4	Yes					
515	Effectiveness (Steel Protective Coatings)	sq feet	4	3440	12962	0	1297	1944	16203
515	Steel Protective Coating	sq feet	4	Yes	12962	0	1297	1944	16203



ASSET ID #: 2639

INSPECTION DATE: 8-28-2020



PHOTO #1 BT23 RT-SIDE OVERVIEW



PHOTO #2 RAILING OVER BM6 SP22 BT23= 0.875" (FEB-20 WAS 0.843")



PHOTO #3 CURB GAP OVER BM AT BT23= 1.21" (FEB-20 WAS 1.40" at 51 deg)



PHOTO #4 WEARING SURFACE OVER **BT23**



ASSET ID #: 2639

INSPECTION DATE: 8-28-2020



BM6 (RT-SIDE) AT BT23 PHOTO #5 **OVERVIEW**



PHOTO #6 SPAN 22 BEAM ENDS AT **BT23**



PHOTO #7 BM4 OF SP22 AT BT23= 0.1875 DEFL+ SQUEAK UNDER LOAD



PHOTO #8 BM4 OF SP22 AT BT23= 0.1875 DEFL+ SQUEAK UNDER LOAD (bot view)



ASSET ID #: 2639

INSPECTION DATE: 8-28-2020



PHOTO #8 SWAY BRACING CORNER TO CAP TOP MEASUREMENT OVERVIEW= 17' 7]16"



PHOTO #9 SWAY BRACING CORNER TO CAP TOP MEASUREMENT CLOSEUP= 17' 7]16"



PHOTO #10 BM6 OF SP22 AT BT23= **BEARING GAP**



PHOTO #11 BM6 OF SP23 AT BT23= **BEARING GAP**



ASSET ID #: 2639

INSPECTION DATE: 8-28-2020



PHOTO #12 WIDENING TYP (BT23 SHOWN)



PHOTO #13 BT23 RT-SIDE CAP= ROTATION



BT23 RT-SIDE CAP= 3" PHOTO #14 DECAY



PHOTO #15 BT23 RT-SIDE= 2" HOLE AT BEG END



ASSET ID #: 2639

INSPECTION DATE: 8-28-2020



PHOTO #16 BT23 HELPER PILE 5A= SEVERE PACT RUST IN SHIMS



PHOTO #17 BENT TYP (23 SHOWN)



PHOTO #18 END BENT TYP



PHOTO #19 BM2 OF SP24 ON BT25(END)= 0.125 DEFL + SQUECK



ASSET ID #: 2639

INSPECTION DATE: 8-28-2020



PHOTO #20 BT25 CAP OVER P4= 0.5" OF **CRUSHING**



Site Assessment Form

Version: 1.0 Page 1 of 5

SECTION 1: GENERAL BRIDGE DATA									
(8) Asset ID:	(8) Asset ID: (2) District: (3) County: (9) Bridge Location: Site Assessment Date:								
2639 7 AIKEN 10 MI E OF AIKEN 2019-10-01									
Bridge Coordinates	:								
(16) Latitude: 33	degrees 34	minutes 36.39	seconds	(17) Longitude:	-81	degrees 30	minutes	59.47 seconds	
(7) Facility Carried:		(6) Feature Crossed:			(43, 44)	Bridge Description	n:		
SC 4/	/SC302	S. EDIS	TO RIVE	R		STEEL CON	ITINUOU	S, MULTI-BEAM	
(45) Number of Main Spans:(46) Number of Approach Spans:(49) Structure Length:(52) Structure Width (out-to-out)									
24 0 601 31									

SECTION 2: FIELD NOTES

In this section, include information on items that affect the load rating, such as SIP forms, utilities, attached signs, overlays, etc. Include notes about deterioration of members to be rated. Do not include information that does not affect the load rating, such as minor deck cracking and spalling. Only include site assessment findings which impact the load rating; however, all critical findings should be reported in the attachment "Critical Deficiencies Form" in Bridge Inspection Guidance Document.

Section Loss:

•Span 24 beam 1 at end bent 25, rust scale with section loss (2ft x full width) (1/4in avg rem) on bottom flange, and (2ft x up to full height) (1/8in avg rem) on web, corrosion hole (6in x up to 4in) on web

•Span 24 beam 5 at end bent 25, rust scale with section loss (1ft x full width) (3/16in avg rem) on bottom flange, and (1ft x up to full height) (1/8in avg rem) on web, corrosion hole (10in x up to 4in) on web

•Span 22 beam 2 at bent 23, rust scale with section loss (1ft x full width) (7/16in avg rem) on bottom flange, and (1ft x 3in) (1/8in avg rem) on web, corrosion hole (3in x 2in) on web

•Span 22 beam 3 at bent 23, rust scale with section loss (18in x full width) (3/8in avg rem) on bottom flange, and (18in x up to full height) (1/8in avg rem) on web, corrosion hole (12in x 4in) on web •Span 22 beam 4 at bent 23, rust scale with section loss (30in x full width x down to knife edge) (3/16in avg rem) on bottom flange, and (30in x up to full height) (1/8in avg rem) on web, corrosion hole (18in x up to full height) on web

•Span 22 beam 5 at bent 23, rust scale with section loss (18in x full width) (7/16in avg rem) on bottom flange, and (1ft x 4in) (1/8in avg rem) on web, corrosion hole (2in x 2in) on web

•Span 21 beam 4 at bent 21, rust scale with section loss (2ft x full width) (7/16in avg rem) on bottom flange, and (2ft x 6in) (1/4in avg rem) on web, no hole on web

•Span 20 beam 4 at bent 21, rust scale with section loss (1ft x full width) (3/8in avg rem) on bottom flange, and (1ft x 3in) (1/8in avg rem) on web, corrosion hole (3in x 1.5in) on web •Span 20 beam 1 at bent 21, rust scale with section loss (18in x full width x down to knife edge) (3/8in avg rem) on bottom flange, and (1ft x up to full height) (3/16in avg rem) on web, no hole on web

• Span 18 beam 3 at bent 19, rust scale with section loss (18in x full width x down to knife edge) (3/16in avg rem) on bottom flange, and (18in x up to full height) (1/8in avg rem) on web, corrosion hole (18in x 3in) on web

•Span 18 beam 4 at 1ft from bent 19, rust scale with section loss (1ft x full width) (1/4in avg rem) on bottom flange, and (1ft x 2in) (1/8in avg rem) on web, corrosion hole (12in x 2in) on web •Span 18 beam 5 at bent 19, rust scale with section loss (5ft x full width) (3/8in avg rem) on bottom flange, and (5ft x 3in) (1/8in avg rem) on web, corrosion hole (8in x 2in) on web at 3ft from bent 19

•Span 18 beam 6 at bent 19, rust scale with section loss (18in x full width) (1/4in avg rem) on bottom flange, and (18in x 4in) (1/8in avg rem) on web, corrosion hole (1in x 1.5in) on web •Span 16 beam 1 at bent 17, rust scale with section loss (1ft x full width) (1/4in avg rem) on bottom flange, and (1ft x 2in) (5/16in avg rem) on web, no hole on web •Span 16 beam 4 at bent 17, rust scale with section loss (1ft x full width) (1/4in avg rem) on bottom flange, and (1ft x 2in) (5/16in avg rem) on web, no hole on web •Span 16 beam 2 at bent 15, rust scale with section loss (1ft x full width) (1/4in avg rem) on bottom flange, and (1ft x up to full height) (1/4in avg rem) on web, corrosion hole (0.5in diameter) on web •Span 14 beam 5 at bent 15, rust scale with section loss (1ft x full width) (1/4in avg rem) on bottom flange, and (1ft x up to full height) (5/16in avg rem) on web, no hole on web •Span 13 beam 3 at bent 13, rust scale with section loss (2ft x full width) (5/16in avg rem) on bottom flange, and (1ft x 4in) (5/16in avg rem) on web, corrosion hole (1in diameter) on web •Span 13 beam 1 at bent 13, rust scale with section loss (2ft x full width) (5/16in avg rem) on bottom flange, and (1ft x 3in) (5/16in avg rem) on web, no hole on web •Span 13 beam 3 at bent 11, rust scale with section loss (2ft x full width) (5/16in avg rem) on bottom flange, and (1ft x 4in) (5/16in avg rem) on web, no hole (1in diameter) on web •Span 10 beam 3 at bent 11, rust scale with section loss (2ft x full width) (7/16in avg rem) on bottom flange, and (1ft x up to fill) (1/8in avg rem) on web, corrosion hole (3in x 2in) on web •Span 6 beam 3 at bent 7, rust scale with section loss (2ft x full width) (1/4in avg rem) on bottom flange, and (1ft x up to fill) (1/8in avg rem) on web, corrosion hole (2in x 4in) on web •Span 6 beam 4 at bent 7, rust scale with section loss (2ft x full width) (1/4in avg rem) on bottom flange, and (1ft x up to fill) (1/8in avg rem) on web, corrosion hole (2in x 4in) on web •Span 6 beam 4 at bent 7

•Span 4 beam 3 at bent 5, rust scale with section loss (2ft x full width) (7/16in avg rem) on bottom flange, and (1ft x 4in) (1/8in avg rem) on web, corrosion hole (4in x up to 4in) on web
•Span 4 beam 4 at bent 5, rust scale with section loss (2ft x full width) (1/4in avg rem) on bottom flange, and (1ft x up to full height) (1/8in avg rem) on web, corrosion hole (4in x up to 6in) on web
•Span 4 beam 4 at bent 5, rust scale with section loss (2ft x full width) (1/4in avg rem) on bottom flange, and (1ft x up to full height) (1/8in avg rem) on web, corrosion hole (4in x up to 6in) on web
•Span 3 beam 4 at bent 3, rust scale with section loss (5ft x full width) (1/4in avg rem) on bottom flange, and (2ft x 2in) (1/8in avg rem) on web, corrosion hole (4in x 2in) on web
•Span 3 beam 1 at bent 3, rust scale with section loss (5ft x full width) (1/4in avg rem) on bottom flange, and (18in x 3in) (1/8in avg rem) on web, no hole on web
•Span 2 beam 4 at bent 3, rust scale with section loss (18in x full width) (1/4in avg rem) on bottom flange, and (18in x 3in) (1/8in avg rem) on web, corrosion hole (2in x 1in) on web
•Span 2 beam 4 at bent 3, rust scale with section loss (18in x full width) (1/2in avg rem) on bottom flange, and (18in x 3in) (1/8in avg rem) on web, corrosion hole (2in x 1in) on web
•Span 2 beam 2 at bent 3, rust scale with section loss (1ft x full width) (1/2in avg rem) on bottom flange, and (1ft x 1in) (5/16in avg rem) on web, corrosion hole (2in x 1in) on web
•Span 1 beam 1 at end bent 1, rust scale with section loss (1ft x full width) (1/2in avg rem) on bottom flange, and (1ft x 1in) (5/16in avg rem) on web, corrosion hole (2in x 1in) on web
•Span 1 beam 1 at end bent 1, rust scale with section loss (1ft x full width x down to knife edge) (3/8in avg rem) on bottom flange, and (4in x 6in) (1/8in avg rem) on web, corrosion hole (2in diameter) on web

NOTE: All beams ends of every (2-span continuous) have rust scale with (up to 1/8in loss) on bottom flanges and (up to 1/16in loss) on web. These locations were not as severe as the areas listed above.



Site Assessment Form

				Page 2 of 5
(8) Asset ID:	District:	(3) County:	(9) Bridge Location:	Site Assessment Date:
2639	7	AIKEN	10 MI E OF AIKEN	2019-10-01
In this section in	oclude information	(if percessary) such as field m	CTION 3: ADDITIONAL NOTES	not recorded during initial site visit load
testing recommendations, etc. Include information on specialized equipment, traffic control, or other needs to perform secondary Site Assessment.				
Temporary	Repair Plat	tes on beam ends		
• Spa	n 12 beam :	3 at bent 13		
• Spa	n 15 beam 3	3 at bent 15		
 Span 16 beam 3 at bent 17 				
Span 17 beam 3 at bent 17				
 Span 18 beam 4 at bent 19 				
Span 21 beam 3 at bent 21				
Span 23 beam 3 at bent 23				
Span 23 beam 4 at bent 23				
Span 10 beam 4 at bent 11				
Span 9 beam 3 at bent 9				
Span 9 beam 4 at bent 9				
Span 7 beam 3 at bent 7				
• Spa	n 7 beam 4	at bent 7		
• Spa	n 2 beam 3	at bent 3		
Timber Ca	ns:			
Bent 23 ca	p rotation u	nder beams 5 and	6 with gap (1/2in) between beams and	l top of cap
Utilities:				
3.5" steel p	pipe attache	d to beam 1		


Site Assessment Form

(8) Asset ID:	District:	(3) County:	(9) Bridge Location:	Page 3 of 5 Site Assessment Date:					
2639	7	AIKEN	10 MI E OF AIKEN	2019-10-01					
SECTION 4: FIELD SKETCHES									
if necessary. Schematic Drawings for bridges without plans shall be a separate document.									
	Liefd Sketch 14 15 15 16 18 18 18 18 18 18 18 18 18 18	28 18 18 18 19 1 1 1 1 1 1 1 1 1 1 1 1 1	$\frac{15^{11} (1r. Rdwy)}{1}$ Ruil h Ruil = 31,5 ¹ Out h Out = 55.75 ¹ Overhags = 3.75 ¹ Deck = 7 ¹¹ 1 (oucrete Diaphagay (Ruy 1+ (17 ¹¹ hally R ⁴¹ wide) (5.5 ¹ spacing)(5 ¹ true en (2+5) (3+4) Prior (original) Interior	Description (2) DATA WORKSHEET (5 File Name Date					
	Bridge Inspection	17%" Vin	7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7'/4" 7	Title BR 2 6 39 Bridge No Drewn By					

Version: 1.0



				Page 4 of 5
(8) Asset ID:	District:	(3) County:	(9) Bridge Location:	Site Assessment Date:
2639	7	AIKEN	10 MI E OF AIKEN	2019-10-01

SECTION 5: PHOTOGRAPHS

Include photos of information to assist with the load rating only. Also include photos of postings for weight or other restrictions, e.g. signs showing "1-Lane Bridge". Do not include photos of defects such as minor deck cracking and spalling. Do not include general photos of the bridge that are in typical inspection reports.



Typical section loss with holes on web. See table condition for more details Typical section loss with holes on web. See table condition for more details



SCE



Version: 1.0

Typical section loss with holes on web. See table condition for more details Typical section loss with holes on web. See table condition for more details



Temporary repair plates throughout. See table for locations Bent 13 pile 3 south face at base, decay (10in x 5ft x 3in) (sister pile attached)



Site Assessment Form

Version: 1.0

(8) Asset ID:	District:	(3) County:	(9) Bridge Location:	Page 5 of 5 Site Assessment Date:				
2639	7	AIKEN	10 MI E OF AIKEN	2019-10-01				
SECTION 5: PHOTOGRAPHS								
not include photos of	is of defects such as mino	the load rating only. Also r deck cracking and spalling	46	ele signa showing la tané bridge a bo cal inspection reports.				
Rotation	n on bent 23 cap	under beams 5 a	nd 6 Gap between beams a	and cap at bent 23				
	NE LOAD M WEIGHT 2 AXLES 3 AXLES 4 AXLES 5+ AXLE	W DTICE LIMIT 16 T 24 T 26 T 5 34 T						
	Posting	sign	3.5" steel pipe attac	ched to beam 1				



Site Assessment Form Supplement



