



SOUTH CAROLINA  
 DEPARTMENT OF HIGHWAYS AND PUBLIC TRANSPORTATION  
 P.O. BOX 191  
 COLUMBIA, S.C. 29202

DANIEL P. FANNING  
 EXECUTIVE DIRECTOR

**INSTRUCTIONAL BULLETIN NO. 94-6**

**SUBJECT:** Underground Storage Tanks  
**EFFECTIVE DATE:** April 15, 1994  
**SUPERSEDES:** New  
**RE:** None


**Superseded  
 by 1994-9**

In the past, underground storage tanks were contracted by the Right of Way Section to be removed and disposed of prior to a road project being let to contract. Underground storage tanks must now be removed as part of the road contract; therefore, they will need to be set-up as "Removal and Disposal Items" in the road plans. They may be combined with other "Removal and Disposal Items" that are on the same tract but must contain their own location (station number and offset left or right), accurate description (i.e. 10,000 gallon kerosene tank), and Work to be done (remove and dispose of tank according to DHEC regulations). They will be shown on the "Removal and Disposal Items" sheet and plotted as accurately as possible on the plan sheets.

Three additional items will be required and quantities will be furnished to Road Design by the Right of Way Agent. They are:

<u>Pay Item No.</u>	<u>Description</u>	<u>Quantity</u>
2021200	Removal and Disposal of Tank Contents	Gallon
2021205	Removal and Disposal of Low Level Contaminated Soil	Ton
2021210	Removal and Disposal of High Level Contaminated Soil	Ton

These three bid items will be shown in the "General Construction Note" (where directed by the Engineer) and on the "Summary of Estimated Quantities" sheet only.

**APPROVED:**   
 E. S. Eargle  
 Road Engineer-Design