



South Carolina
Department of Transportation

955 Park Street
Post Office Box 191
Columbia, South Carolina 29202-0191

Office of the Executive Director
(803) 737-1302 • Fax (803) 737-2038

State Highway Engineer
(803) 737-1314 • Fax (803) 737-2038

Chief Financial Officer
(803) 737-1240 • Fax (803) 737-2014

Director of Mass Transit
(803) 737-9720 • Fax (803) 737-9739

April 13, 1998

INSTRUCTIONAL BULLETIN NO. 98-3

SUBJECT: Additional Alternate Pipe Note

EFFECTIVE DATE: April 8, 1998

SUPERSEDES: None


RE: Revised Instructional Bulletin No. 95-14, Part 3 as noted below

An additional alternate pipe note (shown below) has been added to the cell: APIPE. The cell is placed on the "General Construction Note" Sheet when alternate pipe is specified.

Corrugated Aluminum Alloy Pipe & Corrugated High Density Polyethylene Pipe for sidelines must have cast in place concrete pads to match the adjacent slopes as shown in Standard Drawing No. 802-1.

No separate payment will be made for providing these cast in place concrete pads.

Approved: _____


E. S. Eagle
Road Design Engineer

ESE:adf

cc:

Federal Proj. Dev. Engr. Pratt
"C" Proj. Dev. Engr. Kneece